

REPORT of SURVEY for REPAIRS.

No. 457 Survey held at London Date 12th July 1849
 on the Ship "Royal George" Master T. Green
 Tonnage 486 Built at Killybegs When built 1820
 By whom built — Owners J Marshall
 Port belonging to London Destined Voyage St Philip
 If Surveyed Afloat or in Dry Dock in Swanwick Dock

Last Survey, No. 14273 Port London Classed *A. 1 S.S. 47

REPAIRS at Present from Damage bottom stripped false keel
 new aft & forward ^{double} bottom Cuerned and resheathed
 with Yellow Metal — and not from Damage
 Part of four strakes of hold Ceiling next under the Clamps
 removed timbers exposed sound and good — hanging knees
 taken down & refitted New Ceiling brought of Part
 Cuba hard wood Part Dauty oak treenailed thro' the
 doubling — belye Planks thro' bolted with 36 Yellow Metal
 bolts on each side — the Ceiling in the tween decks
 has been removed abate the Main Mast on both sides and
 Part new ^{strips} shifts of topsides and sheer strakes brought
 with several new filling timbers on both sides Ceiling
 renewed of Cuba hard wood and Dauty oak and
 Present Condition of the old iron hanging knees refitted with 4 pairs new ^{Power}

Decks	Good	Treenails	Part new Good	Windlass and Capstan	Good
Waterways	—	Breasthooks and Stemson	one new	Pumps	—
Comings	—	Transoms, Pointers, and Crutches	—	Boats	—
Upper Deck Beams & Fastenings	Partly new	Timbers of the Frame	When seen	Masts, Yards, &c.	Sufficient
Lower Deck Beams & Fastenings	Partly new	Keelsons	—	Sails	—
Plank sheers	Good	Clamps and Shelves	—	Anchors No. of	—
Sheerstrakes	Part new Good	Ceiling	Much new	Cables	—
Topsides	—	Rudder	—	Hawsers and Warps	—
Wales	Good	Copper	Ym When put on June 1849	Standing & Running Rigging	—
Plank (Bottom) and Counter	Double				
General Observations and Opinion,	Diagonally 1844				

This Vessel is in efficient Condition and
 fit for the safe conveyance of dry and
 perishable Cargoes to & from all Ports of

The Amount of Fee.....£ 2 : — is received by me, the Worts and may
 Special..... 4 : 6 : — remain as Classed
 Certificate (if required) : 10 : — *A. 1 with asterisk

Committee's Minute 1. 2. 8 1849

Character assigned A. 1

Special Damage £4. 4s

15513 Lon

long addition iron knees fitted in the ~~lower~~ ^{upper} decks and
2 pairs to the Stern frame & quarters and a long iron
breast hook also in the ~~lower~~ ^{upper} decks. - New House
Pipe fitted - Hull, Masts, & Rigging generally
overhauled and refitted.

J. H. Ritchie