

REPORT of SURVEY for REPAIRS.

No. 102 on the *Bk "Crator"* Survey held at *London* Date *Oct 3 to Oct 15 1849*
Master *J Homan*
Tonnage *321* Built at *Sunderland* When built *1835*
By whom built _____ Owners *J Allan*
Port belonging to *London* Destined Voyage _____
If Surveyed Afloat or in Dry Dock *In Buildy & Co Nelson Dry Dock*

Last Survey, No. *14324* Port *London* Classed *11 A 1*

REPAIRS *at the present time of damage sustained by being on shore near the Cattegat, more particulars in Special Report.*

The Copper Sheathing stripped off, Ship hung in Shoris, Caulked from upper edge of Wales to keel about 100 started Treennails replaced in After Body below, three additional Bolts thro' After Deadwood and Keel, Rudder repaired, Rudder hangings secured and the Bottom Sheathed with Yellow Metal upon Felt: was thick Paper before.

Not of accident. a new upper piece of Stem Post 12 feet long with a scarp of 12 feet below extending to the keel East India Truss, twelve Stakes of Bottom next below the Wales newly Treennailed thro' all, seven Fair Sticks of Ceiling next the Keelson on the Starboard side and one on the Port side replaced with new one new Timber and others repaired in way of new Ceiling, a new lower Breast Hook of Iron in lieu of Oak, Hold Ceiling extra fastened and repaired.

Present Condition of the

{ Main Mast and Rigging new at St. Petersburg and five new Planks of Deck on the last voyage

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper Metal	Standing & Running Rigging
Plank (Bottom) and Counter	When put on <i>now new upon Felt</i>	

General Observations and Opinion,

This Barque now appears to be in good condition, eligible to remain as Classed A 1

The Amount of Fee.....£ 2 : : is received by me,

Special..... 3 : 3 : -

Certificate (if required) : :

Committee's Minute *23rd Oct 1849*

Character assigned *Cont 4 A 1*

Special Report & £3-3-0 on Damage



© 2019

Lloyd's Register Foundation