

15085

REPORT of SURVEY for REPAIRS.

No. 246 Survey held at London Date Dec 6 to 20 1844
on the By Bolivar Master Barron
Tonnage 204 Built at Whitehaven When built 1824
By whom built _____ Owners Greathend
Port belonging to London Destined Voyage St Vincent
If Surveyed Afloat or in Dry Dock Timekiln Slip

Dec 1/44

st Survey, No. 15224 Port of London SS. 46 Classed A, 1 No Series

PAIRS Present time scraped bright, treenails & bolts driven out for examination
new decks, one new deck beam, new after piece of keelson 26 feet, an
additional Iron patch, deadwood filled up aft between the heels
of the cant timbers & through bolted, ceiling repaired, all the bolts of
lower deck shelf driven out & renewed with Yellow Metal, all the
throat bolts of the Iron hanging knees renewed, topsides & shear shakes
re-treenailed, copper patched & a general overhaul

ent Condition of the

ks <u>new</u>	Treenails <u>good</u>	Windlass and Capstan <u>good</u>
terways <u>good</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>"</u>
nings <u>"</u>	Transoms, Pointers, and Crutches <u>good</u>	Boats <u>"</u>
per Deck Beams & Fastenings <u>"</u>	Timbers of the Frame <u>good where seen</u>	Masts, Yards, &c. <u>"</u>
per Deck Beams & Fastenings <u>"</u>	Keelsons <u>good</u>	Sails <u>well found</u>
anksheers <u>good</u>	Clamps and Shells <u>"</u>	Anchors No. of 3 Bowers 1 Stm 2 Hedge
erstrakes <u>"</u>	Ceiling <u>"</u>	Cables <u>well found</u>
psides <u>"</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
ales <u>"</u>	Copper <u>Y/M</u> When put on <u>1847</u>	Standing & Running Rigging <u>good</u>
ank (Bottom) and Counter <u>good</u>		

General Observations and Opinion, From her good & efficient condition we are of opinion she is fit
for the safe conveyance of dry & perishable cargoes to & from
all parts of the world and may continue as classed A, 1 No Series
with the distinction of SS

The Amount of Fee.....£ 1 : - : - is received by me,

Special..... 3 : 3 : 0

Certificate (if required) _____

Committee's Minute 8th Jan'y 1850

Character assigned A, 1 No Series



© 2019

Lloyd's Register
Foundation

CON627-0418