

REPORT of SURVEY for REPAIRS.

15766

No. 309 Survey held at London Date 26 June 1849
 on the Ship Duke Wellington Master Miller
 Tonnage 457 Built at Dumbarton When built 1842
 By whom built _____ Owners Russell
 Port belonging to Glasgow Destined Voyage Adelaide
 If Surveyed Afloat or in Dry Dock in Messrs. Fitchers Dock

Last Survey, No. 14423 Port London Classed 10 A 1

REPAIRS at present bottom stripped hung in Shores & treenails from the keel to the gunwale all old iron under bolts renewed of yellow metal two lower breast hooks taken down and stemson knee timbers fore hoods of hold ceiling taken up and lower timbers of fore part body cleaned down and six new lower futtocks or filling timbers fitted and several new Cheeks to ditto and new ceiling brought with one new long iron hook and one wood ditto refitted. one length new keelson under main ship and new hog from fore hatchway to main ship. Caulked all over and bottom sheathed with yellow metal on felt above and on paper below. Hull, Masts and Rigging generally overhauled & refitted

Present Condition of the

Decks <u>Good</u>	Treenails <u>all new</u>	Windlass and Capstan <u>Good</u>
Waterways <u>—</u>	Breasthooks and Stemson <u>new Good</u>	Pumps <u>—</u>
Comings <u>—</u>	Transoms, Pointers, and Crutches <u>Good</u>	Boats <u>four</u>
Upper Deck Beams & Fastenings <u>in front bottom new of yellow metal</u>	Timbers of the Frame <u>—</u>	Masts, Yards, &c. <u>sufficient</u>
Lower Deck Beams & Fastenings <u>ditto</u>	Keelsons <u>partly new</u>	Sails <u>—</u>
Planksheers <u>—</u>	Clamps and Shelves <u>Good</u>	Anchors No. of <u>3.1.1</u>
Sheerstrakes <u>all treenailed</u>	Ceiling <u>new forward</u>	Cables <u>—</u>
Topsides <u>and</u>	Rudder <u>Good</u>	Hawsers and Warps <u>—</u>
Wales <u>—</u>	Copper <u>Y.M.</u> When put on <u>same</u>	Standing & Running Rigging <u>—</u>
Plank (Bottom) and Counter <u>caulked</u>		

General Observations and Opinion,

This Vessel is in efficient Condition and may remain as Clipped

The Amount of Fee.....£ 2 : — : — is received by me,

Special..... 2 : 2 : — 18/2/50

Certificate (if required) — : — : —

Committee's Minute 19th July 1850

Character assigned 10 A 1

Special £2.2 record refitted



© 2019

Lloyd's Register Foundation

LON 628-0068