

# REPORT of SURVEY for REPAIRS.

15859

No. 265 Survey held at London Date Feb 12 to Mar 12 1850  
 on the B<sup>re</sup> Maria Somes Master H Naylor  
 Tonnage 600 Built at Yarmouth When built 1841  
 By whom built J. Preston Owners Miss<sup>rs</sup> Somes  
 Port belonging to London Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock In Miss<sup>rs</sup> Somes Dry Dock

Last Survey, No. 14442 Port London Classed 12 A 1

## REPAIRS

at the present time of damage sustained by striking on a Bank in Whampoa River. More particulars in Special Report  
 a new Four piece of False Keel, Copper sheathing stripped off ship hung in shous Caulked from Keel to upper Black Stake, the Bottom sheathed with Yellow Metal upon Felt. 21 feet of Limber Stake on each side in midship replaced a Floor in midship which was slightly sprung repaired and strengthened by extra Bolting it and the Floor on each side it.

Not of accident. 30 feet of Upper Sheer Stake and 30 feet of Planks here new of C. I. Teak in midship on the Port side the original (Fernando Po) being damaged Timbers in way of the above good. Three after hoods in the Port Buttock new, and two in the Starboard Buttock joined

## Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>good</u>	Breasthooks and Stemson } <u>good where seen</u>	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. } <u>In good order and sufficient</u>
Lower Deck Beams & Fastenings } <u>d<sup>o</sup> where seen</u>	Keelsons } <u>d<sup>o</sup></u>	Sails
Plank sheers	Clamps and Shelves } <u>d<sup>o</sup></u>	Anchors No. of
Sheerstrakes } <u>d<sup>o</sup></u>	Ceiling } <u>d<sup>o</sup></u>	Cables
Topsides } <u>d<sup>o</sup></u>	Rudder } <u>d<sup>o</sup></u>	Hawsers and Warps
Wales } <u>d<sup>o</sup></u>	Copper Metal } <u>When put on <u>now new</u></u>	Standing & Running Rigging
Plank (Bottom) and Counter } <u>d<sup>o</sup></u>	Upon Felt	

## General Observations and Opinion,

This Barque now appears to be in good condition eligible to remain as classed A 1

The Amount of Fee.....£ 3 : - : - is received by me,

Special..... 4 : 4 : -

Certificate (if required) \_\_\_\_\_

Committee's Minute 19<sup>th</sup> March 1850

Character assigned 12 A 1

Special Report of £44.00  
 on Damage

recorded as repair



© 2019

Lloyd's Register  
 Foundation  
 LON 628 - 0162