

15884

REPORT of SURVEY for REPAIRS.

No. 549 on the 13th Emily Survey held at London Date March 6th 1850
Master Harvey
Tonnage 400 Built at Calcutta When built 1830
By whom built _____ Owners Luscombe & Co
Port belonging to London Destined Voyage _____
If Surveyed Afloat or in Dry Dock In Mess^r James' Dry Dock

Rec'd 19 Mar

Last Survey, No. 306 Port Swansea Classed 12 * A 1

REPAIRS

40

Now done in compliance with Special Survey Rule for Continuation Sec N^o 54.

The Outside Planking from lower part of Wales upward scraped bright, Iron Bolts driven out at various parts for examination; the Yellow Metal Sheathing stripped off the Bottom and renewed upon bare Doubling; Bottom Caulked and Butts of Wales; slight repair to Doubling in Flat of Bottom where it had been chafed; the Gripe secured by struts thro' Bolts.

The Decks, Coamings, Upper and Lower Deck Bolts, inside and Outside Planking, Plank sheer, Watway, Beams, Knees, Hooks, Knight heads, Haulse Timbers, Keel, Keelson, Transoms, Floors and Timbers of the Frame where they may be seen have been examined by us and are in good condition.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper Metal	Standing & Running Rigging
Plank (Bottom) and Counter	When put on <u>now new</u>	

General Observations and Opinion,

This Barque has now been specially surveyed by us in accordance with Rule Sec N^o 54 and we are of opinion that she is in good condition fit for the safe

The Amount of Fee.....£ 5 : - : is received by me,
Special..... 3 : 3 :
Certificate (if required) : 10 : -
Commencement of dry and perishable cargo to be received from all parts of the world eligible to be continued A 1 for four years from 1840

Committee's Minute 26th March 1850

Character assigned WPA
Special Sec or Continuation } £
A. J. 1840 rec'd
J. Martin
Lloyd's Register
Foundation
LONG28-0187