

REPORT of SURVEY for REPAIRS.

15895

No. 234 Survey held at London Date 18 20 March 1850
 on the Brigantine "Nancy" Master Jen Court
 Tonnage 154 Built at Sunderland When built 1839
 By whom built _____ Owners Forster & Co
 Port belonging to London Destined Voyage Africa
 If Surveyed Afloat or in Dry Dock on Wests Ways

Last Survey, No. 13616 Port London Classed A. 1

REPAIRS

at present bottom stripped & scraped bright from the lower part of the wales to the gunwales 2 new planks in the wales and one plank in starboard buttock timbers exposed good - treenails all renewed from the yellow metal sheathing to the gunwales - and the throat bolts of upper deck knees renewed - Caulked from the keel to the waterways and bottom sheathed with yellow metal on full - all the requisites of Rules Sect 54 Complied with the deck & Comings the upper & lower deck bolts and planks thro which they pass the plank sheer waterways & beams the house timbers, Knight heads, breasthooks, & transoms the floors, & Ribs on the Ceiling & frame inner surface of the outside plank where secured the general form weathered new from wales up

Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	---	Breasthooks and Stemson	Good	Pumps	---
Comings	---	Transoms, Pointers, and Crutches	---	Boats	---
Upper Deck Beams & Fastenings	---	Timbers of the Frame	---	Masts, Yards, &c.	Sufficient
Lower Deck Beams & Fastenings	---	Keelsons	---	Sails	---
Plank sheers	Scraped bright	Clamps and Shelves	---	Anchors No. of	2
Sheerstrakes	retreanated	Ceiling	---	Cables	---
Topsides	and	Rudder	bands thro fast	Hawsers and Warps	---
Wales	Caulked	Copper	Ym	Standing & Running Rigging	---
Plank (Bottom) and Counter	---	When put on	March 1850		

General Observations and Opinion,

This Vessel is in efficient Condition and in our Opinion fit to be Continued on the first class for the longest period Prescribed by the Rules

The Amount of Fee.....£ 2 : : is received by me, Say from 1849 3 yrs A 1
 Special..... 3 : 3 : J D

Certificate (if required) : : :

Committee's Minute 2^d April 1850

Character assigned Cont D 1 for 3 Yrs from 1849
 J D



Lloyd's Register Foundation
 LON 628 - 0199