

# REPORT of SURVEY for REPAIRS.

No. 102  
on the

Survey held at

London

Date

March 10th 1850

Tonnage

513

Built at

London

When built

1826

By whom built

Owners

Liscombe & Co.

Port belonging to

London

Destined Voyage

N. Zealand

If Surveyed Afloat or in Dry Dock

In Messrs. Somes' Dry Dock

Last Survey, No.

1357

Port

London

Classed

12 A 1

## REPAIRS

At the present time of damages sustained by stress of weather Collision and grounding in her passage from Callao to London more particulars in Special Report. False Keel new Yellow Metal Sheathing stripped off and renewed upon Felt. Ship hung in Shores Caulked from Wale to Keel. part of Rails, Timbers and fittings of Head new.

Not of accident. All the Treennails in twenty three upper Stakes of Bottom replaced with new; six throat Bolts of Lower Deck knees renewed 16 feet of Bottom Planking on each side replaced with American Elm 20 feet of Hold Ceiling renewed at various parts and 49 feet of Main Keelson now of T. J. Teak under Main Mast; and the Lower Counter Double with East India Teak.

Decks		Treenails <i>part new</i>		Windlass and Capstan	
Waterways	} <i>good</i>	Breasthooks and Stemson	} <i>good where seen</i>	Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings	} <i>in whole seen</i>	Timbers of the Frame	} <i>good where seen</i>	Masts, Yards, &c.	} <i>In good order and sufficient</i>
Lower Deck Beams & Fastenings		Keelsons <i>part new</i>		Sails	
Plank sheers		Clamps and Shells	<i>d<sup>4</sup></i>	Anchors No. of	
Sheerstrakes	<i>d<sup>4</sup></i>	Ceiling	<i>d<sup>4</sup></i>	Cables	
Topsides	} <i>scraped bright</i>	Rudder	<i>d<sup>4</sup></i>	Hawsers and Warps	
Wales		Copper <i>part new</i>	<i>d<sup>4</sup></i>	Standing & Running Rigging	
Plank (Bottom) and Counter	<i>d<sup>4</sup></i>	When put on <i>new new</i>			

## General Observations and Opinion.

This Ship is now in good condition eligible to remain as Classed A 1

The Amount of Fee.....£ 3 : - : - is received by me,

Special..... 4 : 4 : -

Certificate (if required) : 10 : -

Committee's Minute


23rd April 1850

Character assigned

*See S. A.*

Special Report & on Damage

*£ 4-4-0*



© 2019

Lloyd's Register Foundation

LON 628 - 0242