

# REPORT of SURVEY for REPAIRS.

10048

No. 590 Survey held at London Date May 15 to 20 1850  
 on the Steam Ship "Trident" Master J Morris  
 Tonnage 902 Built at London When built 1841  
 By whom built \_\_\_\_\_ Owners Genl Steam Nav Comp<sup>y</sup>  
 Port belonging to London Destined Voyage Leith  
 If Surveyed Afloat or in Dry Dock In Deptford Creek

Recd by May

Last Survey, No. 13539 Port London Classed 12 A 1  
 18 mo 49

REPAIRS At the present time of damage sustained by being in collision with the ship "Kate" more of particulars in Special Report.

Four Iron Stays to Paddle Beams taken off, repaired, and refitted, a new half to Fore Paddle on the Starboard side of E. S. Teak, the Spacing new at fore side of this Beam, two Planks of sheer stake, one of Topside, 30 feet of Plank sheer Iron Plate knees introduced at Paddle Beams on this side 40 feet of Waterway, five Felling Timbers, six Rougher Stations, 100 feet of Deck and the whole outer portion of Paddle Box new. On the Port side 24 feet of sheer stake and a length of Plank sheer (10 feet), and the Paddle Box repaired.

Deck and Outside Planking above the Copper Caulked

Present Condition of the					
Decks			Treenails		Windlass and Capstan
Waterways	} good		Breasthooks and Stemson	} good when	Pumps
Comings			Transoms, Pointers, and Crutches		Boats
Upper Deck Beams & Fastenings	} d <sup>r</sup> in good		Timbers of the Frame	} d <sup>r</sup>	Masts, Yards, &c. } In good order
Lower Deck Beams & Fastenings			Keelsons		Sails } and sufficient
Plank sheers			Clamps and Shelves	d <sup>r</sup>	Anchors No. of
Sheerstrakes	d <sup>r</sup>		Ceiling	d <sup>r</sup>	Cables
Topsides	d <sup>r</sup>		Rudder	d <sup>r</sup>	Hawsers and Warps
Wales	d <sup>r</sup>		Copper } F	When put on 4	Standing & Running Rigging
Plank (Bottom) and Counter	d <sup>r</sup>				

General Observations and Opinion, This Ship is now in good condition and appears eligible to remain as Classed A 1

The Amount of Fee ..... £ : : is received by me, J. S. Martin

Special..... : :

Certificate (if required) : :

Committee's Minute 31<sup>st</sup> May 1850  
 Character assigned 12 A 1

Special Report } £ 4 - 4 - 0  
 or Damage