

REPORT of SURVEY for REPAIRS.

No. 110 Survey held at London Date 21 May 12 Jun 1850
 on the Tch. "Rebel" Master J Long
 Tonnage 130 Built at Yarmouth When built 1833
 By whom built _____ Owners Ogilby & Co
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock on Wests ways
Sr 572 46

Last Survey, No. 14283 Port London Classed 2 A 1 expunged
C 4 48

REPAIRS at present all new deck laid beams exposed
 sound ^{except} the beam clamped on the Starboard side
 forward - 3 Plank new in topsides in the way of
 fore Channel & shelf & bolts on the Starboard side and
 two new ditto on the larboard side one new wale
 plank on the Starboard side in & out bolts renewed
 in the Gang of these Planks - 3 new Planks of Ceiling
 on the larboard bely & 2 new on the Starboard bely
 all of Amer Oak - timbers where seen sound
 several new Chocks fitted - wales topsides and
 sheerstrakes scraped bright and bolts & trenails
 driven out for survey and found sound or renewed
 where necessary all the yellow metal shaken

Present Condition of the where necessary all the yellow metal shaken
 Decks all new Treenails Good Windlass and Capstan Good
 Waterways Good Breasthooks and Stemson --- Pumps ---
 Comings --- Transoms, Pointers, and Crutches --- Boats ---
 Upper Deck Beams & Fastenings --- Timbers of the Frame --- Masts, Yards, &c. ---
 Lower Deck Beams & Fastenings --- Keelsons --- Sails Sufficient
 Planksheers --- Clamps and Shelves --- Anchors No. of De
 Sheerstrakes Scraped Ceiling Partly new Cables De
 Topsides bright Rudder --- Hawers and Warps De
 Wales Caulked Good Copper Ym When put on June 1850 Standing & Running Rigging De
 Plank (Bottom) and Counter _____

General Observations and Opinion,
 This Vessel is now in efficient Condition
 fit for the safe conveyance of dry & perishable
 Cargoes to & from all Parts of the World
 The Amount of Fee... £ 10 : - is received by me,
 Special... 3 : 3 : -
 Certificate (if required) : 5 : -
 and eligible to be
 Classed A 1 with
 interest on
Stitchie

Committee's Minute 2nd July 1850
 Character assigned A 1
 Lloyd's Register
 Foundation
 LON 622-0411

16103 Lon

Stripped off and the Vessel Caulked all over
and bottom. Leaked like yellow metal
all the Regiments of Tubes Sect 52 & 60 Completed
with the general form & then appear weathered
the Hull, Masts, & rigging generally overhauled
and refitted

J. H. H. H.
To four times



© 2019

Lloyd's Register
Foundation