

# REPORT of SURVEY for REPAIRS.

16134

No. 492 Survey held at London Date July 6 1850  
 on the S Mary Catherine Master J Warner  
 Tonnage 345 Built at Sunderland When built 1836  
 By whom built \_\_\_\_\_ Owners H Nathan  
 Port belonging to London Destined Voyage Sydney  
 If Surveyed Afloat or in Dry Dock In Hawks' Bay Dock  
ND 47 S. 1/2 p. 18

Last Survey, No. 14749 Port London Classed 10 R, 1 expunged  
 Cont 46 3 49

## REPAIRS

Now done under Special Survey Rule 54.60 with a view to reclassing \*A.

The Outside Planking from Yellow Metal upwards, Sixty bright Treennails and Iron Bolts driven out for examination 104 feet of Topside Planking Starboard and 50 feet on the Port side new of Cantyrie Fir the Hold Ceiling about Breast Hooks repaired and Fillings introduced betwixt Knight Heads, Hanse Timbers and Apron in way of repaired Ceiling. Fillings introduced betwixt three lower Transoms, and Caulked from Yellow Metal upwards to Waterway Seam. a new Knee of Head

The Deck, Coamings, Deck and Hold Beam Bolts inside and outside Planking, Treennails, Planks, Waterway Beams, Knees, Hooks, Keel, Keelson, Floors, Knight Heads, Hanse Timbers, Transoms and Timbers of the Frame where they may be seen have been examined by us and appear to be in good condition.

Present Condition of the

Decks	Treennails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper <u>YM &amp; F</u> When put on <u>40</u> d	Standing & Running Rigging <u>stuffed and bunkard</u>
Plank (Bottom) and Counter		

General Observations and Opinion,

This Ship has now been Specially Surveyed by us in accordance with Rule Sect 54.60 and we are of opinion that she is in good condition fit for the safe conveyance of dry and perishable Cargoes to and from all parts of the world.

The Amount of Fee.....£ 1 : : is received by me, \*A.

Special..... 3 : 3 : -

Certificate (if required) : 10 : -

Committee's Minute 9th July 1850

Character assigned Fit for service

Special Fee £ 3-3-0

W. H. Woodstock  
 Lloyd's Register  
 Foundation  
 LONG28-0442