

# REPORT of SURVEY for REPAIRS.

10/1/38  
J. J.  
Rec'd 5 July

No. 462 on the B<sup>n</sup> "Clarendon" Survey held at London Date 24 May till July 1850  
Tonnage 450 Built at London Master W Taylor  
By whom built James & Co Owners Hyde Rodgers & Co  
Port belonging to London Destined Voyage S. Leone & Helena  
If Surveyed Afloat or in Dry Dock in Bilbes & West India Docks  
Siprs 46 & 48

Last Survey, No. 2588

Port Chd

Classed 12 SS 1848 expended

REPAIRS

at present all the Planking of the topsides, sheerstrakes, and Planksheers, and the drifts and Planksheers and waterways of Poop & fore Castle and also the Planksheers and waterways of the main deck renewed of Mahogany - all new wrought-iron stanchions of main deck, Poop, and fore Castle and 35 new top timbers on each side & new Knight heads and four new upper deck beams of Mahogany - 4 new upper deck knees of English oak and part new upper deck Clamps - all the in & out bolts of upper deck fastening and also those of the Poop & fore castle renewed thro' the new Planking - one lower deck beam

Present Condition of the

Decks all new Main Deck  
others good & Caulked  
Waterways Good  
Comings 4 new beams 4 new knees  
Upper Deck Beams & Fastenings all in good  
bolts new  
Lower Deck Beams & Fastenings good  
Planksheers all new Mahogany  
Sheerstrakes all new 4" D  
Topsides all new 3" D  
Wales Scraped bright good  
Plank (Bottom) and Counter good

Treenails new from Wales up  
one new new in two D  
Breasthooks and Stemson best good  
Transoms, Pointers, and Crutches good  
Timbers of the Frame —  
Keelsons —  
Clamps and Shelves —  
Ceiling —  
Rudder overhauled  
E & Copper new When put on 1848  
repairs

Windlass and Capstan Good  
Pumps —  
Boats 4 one new good  
new fore mast & bowsprit  
Masts, Yards, &c. best good  
Sails 2 sufficient  
Anchors No. of 3 1 2  
Cables sufficient  
7 1/2 new 100 fms  
Hawsers and Warps best sufficient  
Standing & Running Rigging overhauled good

General Observations and Opinion,

This Vessel is now in most efficient Condition and fit for the safe conveyance of any & every kind of Cargo to & from all parts of the world

The Amount of Fee.....£ 2 : — is received by me,

Special..... 3 : 3 : —

Certificate (if required) : 10 : —

Committee's Minute

Character assigned

12th July 1850  
W Taylor  
J. J.

Classed 12 SS 1850  
expended  
Joseph H. White  
Lloyd's Register  
Foundation  
LONG28-0447



16138 Son

hook new of Iron Culling repaired in two decks  
and hold all new Channels and Chain bolts  
quarter galleries removed & not replaced the middle  
portion of the knee of head renewed & thro bolted -  
all new Main deck new of Yellow Pine new rails  
and bulwarks through bolt rails & cheeks of heads  
refitted house pipes properly replaced - Caulked  
from the yellow metal up over the decks - yellow  
metal sheathing of bottom repaired - New fore  
mast and bowsprit put in - Hull, masts, &  
rigging, generally overhauled & refitted

S. W. Ritchie



© 2019

Lloyd's Register  
Foundation