

# REPORT of SURVEY for REPAIRS.

16142  
H  
Recd 5 July

No. 5 on the Ship "Hate" Survey held at London Date 24 May 3 June 1850  
Tonnage 786 904 Built at Quebec Master Brodie  
By whom built Owners Marshall  
Port belonging to London Destined Voyage Sydney  
If Surveyed Afloat or in Dry Dock in London & Landward Docks

Last Survey, No. 1521 Port London Classed 5 A 1

REPAIRS at present from Collision with the "Trident" Steamer  
entirely new knee of the head with new Cheeks tails  
and figure also new fore hoods of our Sheerstrake  
two topside one blackstrake and one wale plank on  
the larboard bow 5 new top timbers in the way of Keel  
Port and new Clamps & Ceiling round the larboard  
bow in the two decks one new breast hook & has  
new ceiling fitted over new timbers - the yellow metal  
sheathing stripped off the bows to light water line  
and all the seams from fore rigging on both sides  
caulked - not from damage breacails renewed  
from the wales up to the gunwales

Present Condition of the Lower Deck Decks Caulked	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps New
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper ym When put on 1849	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,  
This vessel is in efficient Condition  
and may continue as Clasp

The Amount of Fee.....£ 3 : - : is received by me, J. H. H. H.  
Special..... 4 : 4 : -

Certificate (if required) : - : -

Committee's Minute 12th July 1850

Character assigned 5 A 1

Special Damage £ 4. 4. -