

# REPORT of SURVEY for REPAIRS.

16158

No. 117 Survey held at London Date 27 June 1850  
 on the Sch. "Elbe Packet" Master J Croft  
 Tonnage 141 Built at Little Hampton When built 1826  
 By whom built \_\_\_\_\_ Owners Williams  
 Port belonging to London Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock on West ways

Last Survey, No. 1505 Port London Classed \* A 1

## REPAIRS

at present from damage by falling over at the  
 Lower Wharf - Ceiling removed on the larboard  
 side from the Keelson to the middle of the 3<sup>rd</sup> futtock  
 amidships and five broken 1<sup>st</sup> futtocks renewed  
 of sound second hand English oak timbers and  
 new Wheel Chocks where uncovered renewed Ceiling  
 renewed part new Ceiling also on the Starboard by  
 treenails renewed two new Ceiling - two pairs of  
 additional iron hanging knees fitted to hold beams  
 bottom Caulked to the wales - and all the damage  
 repaired

## Present Condition of the

Decks	Treenails <u>Partly new</u>	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame <u>Good</u>	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons <u>Good</u>	Sails
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling <u>Partly new</u>	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper <u>None</u> When put on	Standing & Running Rigging
Plank (Bottom) and Counter		

## General Observations and Opinion,

This Vessel is now in efficient Condition  
 and is our opinion fit for the Safe Conveyance  
 of dry and perishable Cargoes to & from all

The Amount of Fee £ : 10 : - is received by me,

Special.....

Certificate (if required) : 5 : -

Committee's Minute

Character assigned

Special Damage £ 2. 2

Parts of the world  
 and fit to remain  
 as Classed \* A 1



© 2019

Lloyd's Register  
 Foundation

LON 629 - 0007