

REPORT of SURVEY for REPAIRS.

Continuation

20/7/50

No. 213 Survey held at London Date July 8th 17 1850
 on the Bk Black River Packet Master E Stamp
 Tonnage 265 Built at Southampton When built 1825
 By whom built _____ Owners Morris & Co
 Port belonging to London Destined Voyage Jamaica
 If Surveyed Afloat or in Dry Dock King & Queen Dock

Last Survey, No. 14414 Lon Port Restored 1843 Classed 7A1

REPAIRS At the present time on the starboard side 80 feet of new black shake 61 feet of lower black shake & 41 feet of sides; on the port side 52 feet of upper black shake 56 feet of lower black shake four new rough pine timbers, 13 new filling timbers abreast of the fore main rigging, all the chain plate & preventer bolts renewed, head refitted, new stem & head knee & caulked from the copper to the gunwale. Several bolts & treenails driven out in various parts & found in good condition as well as the planks through which they pass, the plank sheers, waterway, beams, bawse timbers, knight heads, breasthooks, transoms, floors & keelson, the outside planking & ceiling are all in a sound and efficient state, the keel is straight and has preserved her original form.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shells	Anchors No. of 3 Bowers 1 Stm 2 Kedge
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper	Standing & Running Rigging
Plank (Bottom) and Counter	When put on 1840	

General Observations and Opinion. This vessel has been surveyed as & rule section 54 and from her efficient state we are of opinion she may be continued as long on the list of ships of the first description of the first class as the rules allow say two years At sup. 1850

The Amount of Fee.....£ 3 : : is received by me,

Special..... 3 : 3 : -

Certificate (if required) : : -

Committee's Minute 22nd Nov 1850

Character assigned 7A1