

Continuation

18475

REPORT of SURVEY for REPAIRS.

Change of Owners & Rectifying

No.

57

on the

Survey held at

London

Date

Jan 25

1850

Year

1850

Master

Winter

Tonnage

301
307

Built at

Dundee

When built

1837

By whom built

Owners

Soutter

Port belonging to

London

Destined Voyage

If Surveyed Afloat or in Dry Dock

in Messrs Petchers Dock

Sept 18

Last Survey, No.

1303

Port

Dundee

Classed

Rt 1844 for 5 yrs expunged

REPAIRS

at present bottom stripped 25ft new main
 keelson & 22ft of hog keelson the fore hood of
 the Ceiling Floor breast hook removed and
 8 new lower futtocks fitted New fore hoods of Ceiling
 wrought with one new iron breast hook and two
 iron riders fitted forward several new planks of
 Ceiling amidships - also new Ceiling aft with
 new inner stern post and lower transoms with new
 timbers under transom and an iron transom fitted
 over these new timbers - one pair of new hanging iron
 fitted to after hold beam - Wales doubled with
 2" Amer Elm on felt six strokes on each side with
 3" Cants treenailing of bottom renewed to the keel

Present Condition of the

Decks

Good

Treenails

New in bottom

Windlass and Capstan

Good

Waterways

one new

Pumps

Good

Comings

one new

Boats

Sufficient

Upper Deck Beams & Fastenings

New bolt & nut

Timbers of the Frame

24 new

Masts, Yards, &c.

Do

Lower Deck Beams & Fastenings

Keelsons

Sails

Suff

Planksheers

Scraped bright

Clamps and Shelves

Sufficient

Anchors No. of

3 1 1

Sheerstrakes

Good

Ceiling

450 new

Cables

Sufficient

Topsides

Rudder

Hawsers and Warps

Wales

double

Copper

Yr When put on New

Standing & Running Rigging

Sufficient

Plank (Bottom) and Counter

General Observations and Opinion,

This vessel is in efficient Condition and
 and in our opinion fit for the safe conveyance of
 dry & perishable Cargoes to & from all Parts of the
 world and all the requisites of Rules Sect. 54 have
 been complied with and under Sect. 59 is
 eligible to be Continued
 for 2 yrs from 1849

The Amount of Fee.....£ 4 : - : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) : 10 : -

Committee's Minute

13th Dec 1850

Character assigned

A 1 & 2 years

© 2019

Lloyd's Register
Foundation

LON 629-0334

16475. Jan.

Throat bolts of iron hanging knees renewed
(41 in number) of hold beams - Repl. hung in
shores Caulked from the keel to the 2^d beam of
the deck and bottom sheathed with yellow
metal on felt - hull, masts, rigging generally
overhauled & refitted

J. H. Ritchie
Houston



© 2019

Lloyd's Register
Foundation