

# REPORT of SURVEY for REPAIRS.

No. 119 on the Ship "Wellington" Survey held at London Date 19<sup>th</sup> Nov 4<sup>th</sup> Dec 1850  
 Tonnage 473 Built at Bombay Master Vellacott  
 By whom built Owners Evans & Co  
 Port belonging to London Destined Voyage Adelaide  
 If Surveyed Afloat or in Dry Dock in Messrs Dowson Dock

Last Survey, No. 1371 Port London Classed \*A. 1

## REPAIRS

at present the doubling of ~~the~~ top-sides and sheer-strakes scraped bright and bolts driven out for turning and where defective renewed - the yellow metal stripped off and wood sheathing of the flat of bottom also removed and the bottom Caulked and the doubling of the bottom <sup>on flat</sup> continued down to the keel all the defective ceiling in hold removed and 1100 feet new oak ceiling brought doubling fastened with 1400 brass nails and 600 three bolts of yellow metal two new iron breast hooks fitted and bolted with yellow metal the gale & outer stem removed and middle line bolts renewed in stem & dead wood with yellow metal timbers of frame exposed

## Present Condition of the

Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	---	Breasthooks and Stemson	Good	Pumps	---
Comings	---	Transoms, Pointers, and Crutches	Good	Boats	---
Upper Deck Beams & Fastenings	---	Timbers of the Frame	Do	Masts, Yards, &c.	---
Lower Deck Beams & Fastenings	---	Keelsons	Do	Sails	well found
Plank-sheers	all doubled	Clamps and Shelves	Do	Anchors	No. of 3 Bower Stem & 2 Kedges
Sheerstrakes	in 1842	Ceiling	Much new in hold	Cables	320 fms sufficient size
Top-sides	scraped bright	Rudder	Good	Hawsers and Warps	well found
Staves	Good	Copper	Ym When put on Dec 1850	Standing & Running Rigging	part new
Plank (Bottom) and Counter	part 1850				

## General Observations and Opinion,

This vessel is in good efficient condition and in our opinion fit for the safe conveyance of dry perishable cargoes to & from all parts of the

The Amount of Fee.....£ 2 : - : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) .....


Committee's Minute

20<sup>th</sup> Dec 1850

Character assigned

A. 1

J. H. Ritchie



© 2019 Lloyd's Register Foundation LON 629-0341



16482. Jan.

resheathed with yellow metal. the Counter doubled  
on felt. the Hull generally overhauled all  
the Requisites of Rules Sect 54, 160 Complied with  
all the Original Planking of this Vessel bottom is  
rabbeted together in the most Careful Manner thus

W.

J. H. Ritchie

Forstman



© 2019

Lloyd's Register  
Foundation