

REPORT of SURVEY for REPAIRS.

Continuation

No. 307 Survey held at London Date 10th till 25th Feb 1857
 on the Br Marmion Master Peat
 Tonnage 360 Built at Dartmouth When built 1838
 By whom built _____ Owners Stringer & Mann
 Port belonging to Swanpool Destined Voyage West India
 If Surveyed Afloat or in Dry Dock in Messrs Fitchers Dock

Last Survey, No. 15641 Port London Classed 12 A 1 now A 1

REPAIRS at present Wales, topsides, and sheer strakes scraped bright and bolts and trenails driven out for survey, trenails all renewed in Wales or where found defective washed bolts renewed & part of screw bolts of hold beam renewed - the lower deck hook renewed of English oak and an additional iron hook also fitted in hold, all the Kelson except after length renewed of African oak, ^{E. Indian} yellow metal bolted hold beam under Fall bolt Clamped & bellared, one pair of add'l iron knees fitted to the break of quarter deck new fore mast shipped and yellow metal gatchies C. T. Over

Present Condition of the

Decks	Trenails	Windlass and Capstan
Waterways	<u>too new</u>	<u>new lower</u>
Comings	Breasthooks and Stemson	Pumps <u>parts</u>
Upper Deck Beams & Fastenings	Transoms, Pointers, and Crutches	Boats
Lower Deck Beams & Fastenings	Timbers of the Frame	<u>new fore mast</u> <u>good</u>
Planksheers	Keelsons <u>all new but after</u>	Masts, Yards, &c.
Sheerstrakes	Clamps and Shelves	Sails
Topsides	Ceiling	Anchors No. of
Wales <u>scraped</u>	Rudder	Cables
Plank (Bottom) and Counter	Copper <u>ym</u> When put on <u>1850</u>	Hawsers and Warps
		<u>refilled</u>
		Standing & Running Rigging

General Observations and Opinion,

This vessel is now in efficient Condition and in our opinion fit to be Continued on the first Class for the longest period prescribed by

The Amount of Fee.....£ 4: -: - is received by me, the Club say from

Special..... 3: 3: - 1850. 4th Feb 1

Certificate (if required) : 10: -

Committee's Minute 28th Feb 1857

Character assigned Class 4 A 1

A. Ritchie
Surveyor
 Lloyd's Register
 Foundation

16628 Lon

all the Requisites of Rule Sect 54 Complied
with - The Upper Deck & Covering, the outside
and Culing Planks, the Plank Sheer Waterways
and beams, the main timbers, Mould heads,
breasthooks and transoms, the floors & Keelsons,
and the frame & inner surface of the outside Plank
where seen are sound & good and sheer and
general form ^{appear} unaltered

A. H. H. H.



© 2019

Lloyd's Register
Foundation