

REPORT of SURVEY for REPAIRS.

Continuation

No. 306 Survey held at London Date 1st till 15 April 1857
 on the Ship Marquis of Bute Master Bannatyne
 Tonnage 459 Built at Grunock When built 1841
 By whom built _____ Owners Sharp & Co
 Port belonging to Rothsay Destined Voyage Sydney
 If Surveyed Afloat or in Dry Dock In Duke Shore Dock

Last Survey, No. 1558 Port London Classed 10 A 1

REPAIRS at present bottom stripped & renewed from the bilges to the sheerstrakes. Wales topsides and sheerstrakes scraped bright - two new after hoods of wales brought and 6 after hoods of bottom on the larboard and 7 ditto on the Starboard. Side timbers and transoms exposed & found good - a pair of new heavy transom knees & an iron crutch fitted all the iron lodging knee and shelf bolts of hold beams renewed of iron one additional pair of iron hanging knees fitted amidships to lower deck the ceiling renewed between the breasthooks and aft in the hold. Vessel hung in shows Caulked from Keel to Stow

Present Condition of the

Decks	Good	Treenails	good New test Good	Windlass and Capstan	Good
Waterways	—	Breasthooks and Stemson	Good	Pumps	—
Comings	—	Transoms, Pointers, and Crutches	New —	Boats	Many New test
Upper Deck Beams & Fastenings	bolts renewed of iron	Timbers of the Frame	—	Masts, Yards, &c.	Good
Lower Deck Beams & Fastenings	—	Keelsons	—	Sails	Sufficient
Planksheers	Scraped	Clamp and Shelves	—	Anchors No. of	3 1 1
Sheerstrakes	bright & renewed	Ceiling	renewed whole for 10 ft	Cables	Sufficient
Topsides	and	Rudder	Good	Hawsers and Warps	Do
Wales	Caulked Good	Copper	ym When put on Aft 1857	Standing & Running Rigging	Do
Plank (Bottom) and Counter	—				

General Observations and Opinion,

This Vessel is in efficient and the Requisites of Sect. 54 have been Complied with She is eligible to be Continued on the first Class

The Amount of Fee £ 5 : - : - is received by me, for the longest period prescribed by the Rules say from 1857. 3rd April

Special..... 5 : 5 : -

Certificate (if required) : : :

Committee's Minute 25th April 1857

Character assigned 10 A 1 Cap J. A. 1 James

Special extra £2. 2

© 2019

Lloyd's Register Foundation

LON 630-0116

16732 Lon

Caulked from the Keel up Keel seams & Hooding end
listes with felt and bottom Resheathed with yellow
Metal on felt above & Paper below - New fore and
Mizen Masts (new Main Mast of Teak at Bombay) and
new fore topsail & Crossjack yards New Mizen topsail
& two topgallant yards - The upper deck & Com
the outside & Ceiling Planks the Plank sheers water
and beams' house timbers Knight heads breastho
and transoms the floors & Kelsons the frame and
inner surface of the outside plank where seen
sound and good and the sheer and general form
appear unaltered -

J. H. Ritchie
J. H. Ritchie



© 2019

Lloyd's Register
Foundation