

10805

Recd 19 May

REPORT of SURVEY for REPAIRS.

No. 475 on the *Sc. Slater Nelson* Survey held at *London* Date *April 30 to May 19 1857*
Master *W. Cuming*
Tonnage *112* Built at *W. Ho* When built *1835*
By whom built _____ Owners *Beeco & Co*
Port belonging to *London* Destined Voyage *Mediterranean*
If Surveyed Afloat or in Dry Dock *In Globe Dry Dock*

Last Survey, No. *11225* Port *Lpool* Classed *11 A1*
Cant *49 4* 5mo 50

REPAIRS at the present time of damage sustained by stress of weather and by grounding in her passage from *St Michael's* to *London*, more of particulars in Special Report.

Knee of Head new, Yellow Metal Sheathing stripped off and renewed upon Paper. The bruised underside of Main Keel, trimmed off and a new False Keel introduced. Two Planks of Ceiling lifted at Floor Head Stanch, under Fore Chains to examine Timbers, one being found slightly sprung and two stained six Fillings and one thicker Plank have been introduced with extra thro' Bolting, fully compensating the damage done there. Bottom Planking laid after Deadwood extra Bolted, hung in Shaes Caulked from Keel upwards to Seam of Deck next the Waterway, and one Brace of Rudder new

Not of accident. The Deck Caulked.
Present Condition of the

Decks		Treenails		Windlass and Capstan	
Waterways	} <i>Good</i>	Breasthooks and Stemson	} <i>Good where seen</i>	Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings	} <i>Good where seen</i>	Timbers of the Frame	}	Masts, Yards, &c.	} <i>In good order and sufficient</i>
Lower Deck Beams & Fastenings		Keelsons		Sails	
Planksheers		Clamps and Shelves	<i>d⁴</i>	Anchors No. of	
Sheerstrakes	<i>d⁴</i>	Ceiling	<i>d⁴</i>	Cables	
Topsides	<i>d⁴</i>	Rudder	<i>d⁴</i>	Hawsers and Warps	
Wales	<i>d⁴</i>	Copper	<i>St. Metal</i> When put on <i>now new</i>	Standing & Running Rigging	
Plank (Bottom) and Counter	<i>d⁴</i>				

General Observations and Opinion,

The damage done to this Schooner has now been repaired. She appears to be in good condition eligible to remain as Classed *A1*

The Amount of Fee.....£ — : 10 : — is received by me,

Special..... 2 : 2 : —

Certificate (if required) _____

Committee's Minute *23rd May 1857*

Character assigned *Cant 4*

Special Report *2-2-0*
on Damage