

REPORT of SURVEY for REPAIRS.

Continuation

No. *189* Survey held at *London* Date *24th 25 April 1851*
 on the *Ship "Owen Glendower"* Master *W. Pare*
 Tonnage *911* Built at *London* When built *1839*
 By whom built *R Green & Co.* Owners *R Green*
 Port belonging to *London* Destined Voyage *Bombay*
 If Surveyed Afloat or in Dry Dock *in Mif. Green Dock*

Last Survey, No. *14105* Port *London* Classed *12 A 1*

REPAIRS at Present Wakes, topsides, and sheer strakes, scraped bright, and bolts and trenails driven out for Survey - trenails and bolts good one length of sheerstrake renewed on the Starboard side of ~~quarters~~ ^{of quarters} exposed found sound & good - an additional pair of iron Gougers fitted to the Stern frame - bottom stripped, ^{hung} Caulked and resheathed with yellow metal - decks watertight and hooding ends Caulked - the decks & Comings the outside, & ceiling planks, the Plank sheers, waterways, & beams, the house timbers, Knapthheads, & *of 1000*

Present Condition of the

Decks <i>Good</i>	Trenails <i>Good</i>	Windlass and Capstan
Waterways <i>Caulked</i>	Breasthooks and Stemson <i>one pair added fitted</i>	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings <i>firm</i>	Timbers of the Frame <i>Good</i>	Masts, Yards, &c.
Lower Deck Beams & Fastenings <i>do</i>	Keelsons	Sails
Plank sheers <i>Scraped</i>	Clamps and Shelves	Anchors No. of
Sheerstrakes <i>bright</i>	Ceiling	Cables
Topsides <i>good</i>	Rudder	Hawsers and Warps
Wales	Copper <i>4 1/2</i> When put on <i>April 1851</i>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

This Ship is in efficient Condition and all the requirements of Rules Sect 54 having been complied with we are of opinion she is

The Amount of Fee.....£ 5 : - : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) : 10 : -

Committee's Minute *6th June 1851*

Character assigned *12 A 1 Class 4 A 1*

eligible to be Continued on the first Class for the longest period she is entitled to by the Rules say from 1851 4 1/2 A 1

Wm. Wainwright
J. B. Mitchell
Lloyd's Register Foundation

16834, Jan

and transoms, and breasthooks, the floors, & Keels
and the frame and inner surface of the outside
planks where seen are sound and good and the
sheer and general form appear unaltered. The
masts, & rigging, generally overhauled & refitted.
J. H. Sturges



© 2019

Lloyd's Register
Foundation