

10954

REPORT of SURVEY for REPAIRS.

Change of Owners

No. 370 Survey held at London Date from 9 July till 2 Aug 1857
on the Sh^r Mirondele Master Thos Merald
Tonnage 135 Built at Whitby When built 1835
By whom built _____ Owners Captain R^o
Port belonging to Dundee Destined Voyage Orchangel
If Surveyed Afloat or in Dry Dock in Fore & aft dock

Last Survey, No. 1557 Port Dundee Classed C 10 * A 1 S 50

REPAIRS at present from damage all new, ^{after length of} keel and garboard
strake all the ^{garboard} midship lengths of Ceiling removed
from limbers to 1st futt^{rs} heads and eleven broken
1st futt^{rs} removed & replaced with 7 of English oak
and 4 of Baltic oak, new Ceiling brought over ditto
four planks removed above the bilge on each side
and new Amer Elm brought in their places, 14 filling
fitted between the 1st futt^{rs} on the Starboard bilge and
new Ceiling planks brought over them - 3000 boards
removed in the bottom and wales - two new foreheads
of bottom on Starboard bow where they had been struck
with an anchor - 4 pairs of add^d iron knees fitted
to hold beams before abaft Main hatchway - new Key Holes

Decks	Good	Treenails	3000 New Good	Windlass and Capstan	Good
Waterways	—	Breasthooks and Stemson	—	Pumps	overhauled Good
Comings	—	Transoms, Pointers, and Crutches	—	Boats	one
Upper Deck Beams & Fastenings	new	11 new 1 st futt ^{rs} 14 filling	new top mast	Masts, Yards, &c.	sufficient
4 new iron knees	—	Timbers of the Frame and many Chocks	—	Sails	sufficient
Lower Deck Beams & Fastenings	new	Keelsons	14 new fore	Anchors	No. of 2 1 1
Planksheers	—	Clamps and Shells	Good	Cables	sufficient
Sheerstrakes	renewed	Ceiling	Much new	Hawsers and Warps	Do
Topsides	—	Rudder	Good	Standing & Running Rigging	Do
Wales	Caulked	Copper	None When put on		
Plank (Bottom) and Counter	—				

General Observations and Opinion, This Vessel is in excellent Condition
and in our opinion fit for the safe conveyance
of dry perishable Cargoes & is eligible to

The Amount of Fee.....£ : 10 : — is received by me, Wm Ritchie
Special.....£ : 3 : 3 at office 4/8/57
Certificate (if required) : 5 :

Committee's Minute 2 Aug 1857
Character assigned First class
Special Damage £3.3.
Do Valuation 2.2
Lloyd's Register Foundation
LON 630-0341

16945. Jan.

Wing in Shores, Caulked from Keel up to the Water
Wing Seams —

J. H. H. H. H.
P. C.



© 2019

Lloyd's Register
Foundation