

REPORT of SURVEY for REPAIRS.

17049

No. 120 Survey held at London Date Sept 2 to 17 1851
 on the "Haseemy" Master S. Ross
 Tonnage 523 Built at Calcutta When built 1817
 By whom built _____ Owners Ross & Co
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Afloat in the India Dock, and in Wigram's Dry Dock

Last Survey, No. 14140 Port London Classed * A. 1
S.S. 50 5 mo 50

REPAIRS at the present time, of damage by being on shore in Shalks Bay, and by stress of weather in the passage to London, more of particulars in Special Report.

The yellow metal sheathing stripped off and renewed, ship hung in thous, caulked outside, including the Flat of Upper Deck; the whole of False Keel new, a new Main piece to Rudder; 10 ft of Doubling against after end of Keel each side new; a Pair of Iron Staple Standard, added at after part of Poop, and a pair of Wood Knus at fore part. Bulkheads under Poop repaired, an Iron Hook introduced outside over the Bowsprit, and the Bulwarks &c repaired.

Not of damage A new Beam to Upper Deck, at left side of main Hatchway

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>Good</u>	Breasthooks and Stemson } <u>Good where seen</u>	Pumps
Comings } <u>Good</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>In good order and sufficient</u>
Lower Deck Beams & Fastenings <u>ditto where seen</u>	Keelsons <u>d⁴</u>	Sails
Planksheers	Clamps and Shelves <u>d⁴</u>	Anchors No. of
Sheerstrikes <u>d⁴</u>	Ceiling <u>d⁴</u>	Cables
Topsides <u>Doubled 44 d⁴</u>	Rudder <u>d⁴</u>	Hawsers and Warps
Wales <u>Doubled 33 d⁴</u>	Copper <u>Y Metal</u> When put on <u>new new</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>74 Doubled 33 d⁴</u>		

General Observations and Opinion,

This Vaque now appears to be in good condition, fit for the safe conveyance of dry and perishable cargo to and from all parts of the world eligible to remain

The Amount of Fee.....£ 3 : — : is received by me, as Classed * A. 1

Special..... 5 : 5 : —

Certificate (if required) : 10 : —

Committee's Minute 23rd Sept 1851

Character assigned A 1 1 Stewart

See for Special Report & on Damage £ 5-5-0



Lloyd's Register Foundation

LON 630-0435