

17100

REPORT of SURVEY for REPAIRS.

Continuation

No. 410 on the Brig "Elizabeth Beynon" Master Beynon
Survey held at London Date 13 April 13 Oct 1851
Tonnage 205 Built at Pools When built 1839
By whom built _____ Owners J Beynon
Port belonging to Swansea Destined Voyage _____
If Surveyed Afloat or in Dry Dock on Crisp's ways & Fore and Aft Dock

Rec 23 Oct

Last Survey, No. 444 Port Swansea Classed 12 A 1

REPAIRS at present Wales, topsides, & sheerstrakes. Scraped bright and bolts and trenails driven out for survey and where found defective renewed - one length of sheerstrake renewed on the Starboard side and new topside planks in the line of the chain bolts then pairs of additional iron knees fitted to the upper deck beams, Ceiling repaired, one ~~pair~~ iron knee of hold beam taken down & repaired & refitted. 8 new tough-bru stanchions and part new tail bulwarks fitted bottom stripped, Caulked and tuckered with yellow putty on dry paper - the upper deck & coverings the outside & ceiling planks the plank sheers waterways and floors

Present Condition of the

Decks	Trenails <u>overhauled</u> <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways	renewed <u>Good</u>	Pumps _____
Comings	Breasthooks and Stemson _____	Boats _____
Upper Deck Beams & Fastenings	Transoms, Pointers, and Crutches _____	Masts, Yards, &c. <u>Sufficient</u>
Lower Deck Beams & Fastenings	Timbers of the Frame _____	Sails _____
Plank sheers	Keelsons _____	Anchors No. of _____
Sheerstrakes	Clamps and Shells _____	Cables _____
Topsides	Ceiling <u>repaired</u> <u>Good</u>	Hawsers and Warps _____
Wales	Rudder <u>overhauled</u> _____	Standing & Running Rigging _____
Plank (Bottom) and Counter	Copper <u>fine</u> When put on <u>Oct 1851</u>	

General Observations and Opinion,

This vessel has been surveyed in accordance with the Rules of 1851, and being in efficient condition is eligible to be continued on the first class for the

The Amount of Fee.....£ 3 : - : - is received by me, Period prescribed by the Rules say from 1851. 4/11
Special..... 3 : 3 : -
Certificate (if required) : 10 : -

Committee's Minute 21st Oct 1851
Character assigned 12 A 1
Special Damages £ 8 2

17100 Ton.

and beams the main timbers, Kneightheads, breastworks,
and transoms, the floors & hulls and the frame &
inner surface of the outside planks where seen are sound
and good and the Sheer and general form unaltered

J. H. Ritchie



© 2019

Lloyd's Register
Foundation