

17170

REPORT of SURVEY for REPAIRS.

& to raise class

No. 84 Survey held at London Date Oct 14th to Nov 10th 1851
on the Bk David Suckie Master JR Chase
Tonnage 328 Built at Sunderland When built 1837
By whom built 375 Owners J Suckie
Port belonging to London Destined Voyage Demerara
If Surveyed Afloat or in Dry Dock West India Dock & Fitchew Dock

Survey, No. 10389 Port London Classed A1

With the present time from stress of weather on her passage from Demerara has had 8 new strappings, new bulk head to front of the brake, two new planks of oak in the way of the ring bolts in the deck, new winch bits & cross piece new bulkheads & rails & caulked from the wales to the comings,

Not of damage, new topsides of red pine, one new quarter timber, 2 sheers, counter repaired, lower deck breasthooks rebolted with 1/2 inch 54 lower deck waterway bolts & the throat bolts of the Iron hanging knees to the upper deck renewed, all new preventer bolts to the lower rigging, scraped bright & beenails out for examination found in good condition as well as the planks through which they pass the plank sheers, waterway beams, hawse timbers, knight heads, breasthooks, transoms, floors & keelsons planking outside & inside are all in a good & efficient state

Present Condition of the	Treenails	good	Windlass and Capstan	good
Decks	Breasthooks and Stems	good	Pumps	good
Waterways	Transoms, Pointers, and Crutches	good	Boats	good
Comings	Timbers of the Frame	good where seen	Masts, Yards, &c.	good
Upper Deck Beams & Fastenings	Keelsons	good	Sails	well found
Lower Deck Beams & Fastenings	Clamps and Shelves	good	Anchors	No. of 3 Bower Stern & Kedge
Plank sheers	Ceiling	good	Cables	well found
Sheerstrakes	Rudder	good	Hawsers and Warps	good
Topsides	Copper	When put on 1840	Standing & Running Rigging	good
Wales				
Plank (Bottom) and Counter				

General Observations and Opinion. This vessel has complied with the rule Sect 60 and we are of opinion she is fit for the safe conveyance of dry & perishable cargoes to & from all parts of the world & may be classed A1 with the distinction of the Notch

The Amount of Fee.....£ 2 : - : - is received by me,

Damage Special..... 3 : 3 : 0
Notch " " 3 : 3 : 0
Certificate (if required) : : :

R. M. Dobson
J. H. Ritchie

Committee's Minute 21st Nov 1851

Character assigned A1

