

17228

# REPORT of SURVEY for REPAIRS.

No. 17228 Survey held at London Date Nov 25<sup>th</sup> Dec 11<sup>th</sup> 1851  
on the Stm<sup>e</sup> Caledonia Master H Gibbs  
Tonnage 423 Built at London When built 1836  
By whom built        Owners Gen<sup>e</sup> Stm Nav Comp<sup>y</sup>  
Port belonging to London Destined Voyage         
If Surveyed Afloat or in Dry Dock In Dry Dock Deptford

Last Survey, No. 15758 Port London Classed 11 A 1

REPAIRS <sup>49</sup> at the present time Copper Sheathing stripped off the Bottom, Outside Planking scraped bright from Copper line upwards, Bolts and Treennails out for examination, Boilers taken out, Ceiling, Keelsons & in way of them examined and proved to be sound, Foundation Bolts of Engines new, Standard knees to side Keelson in way of Engine their thro(ron) Bolts replaced with Copper. The Ship Caulked outside, and the Bottom sheathed with Yellow Metal upon Belt.

The Deck, Coamings, Decks and Hold Beam Bolts, inside and outside Planking, Treennails, Planksheer, Waterway Beams, Knees, Hooks, Keel, Keelsons, Knight heads, Flawse Timbers, Floor Transoms, and Timbers of the Frame where they may be seen have been examined and appear to be in good condition.

Decks	Treennails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Vales	Copper	Standing & Running Rigging
Plank (Bottom) and Counter	When put on <u>now new</u>	

## General Observations and Opinion.

This Steamer has now undergone a thorough examination in every respect equal to the requirements of Rule Sec 54860. We are of opinion that she is in good condition, fit for the safe conveyance of dry and perishable cargoes to and from all parts.

The Amount of Fee.....£ 2 : - : - is received by me,


Special..... 3 : 3 : -

Certificate (if required) : 10 : -

Committee's Minute 23<sup>rd</sup> Dec. 1851

Character assigned A 1

Special Fee £ 3-3-0



Lloyd's Register  
Foundation

LON631-0186