

REPORT of SURVEY for REPAIRS.

17283

No. 537 Survey held at London Date Jan^y 31st 1852
 on the S^r Ann Squire Master P. Pater
 Tonnage 161 Built at Dartmouth When built 1845
 By whom built _____ Owners Conroy & Co.
 Port belonging to Dartmouth Destined Voyage Newport
 If Surveyed Afloat or in Dry Dock Fletcher Dock

Last Survey, No. 10800 Port London Classed 12 A1

REPAIRS

Having been on shore on the Tongue sand has been shipped, hung; caulked from the keel to the waterways, a false keel fitted & sheathed with Yellow Metal on felt

Not of damage, new fore piece of keelson, and the two foremost floors being slightly defaced on the upper part, has been chocked & the first forethocks on each side cross chocked, a stemson knee fitted on the fore end of the keelson, & the ceiling repaired,

Present Condition of the

Decks <u>Good</u>	Treenails <u>good</u>	Windlass and Capstan
Waterways <u>Good</u>	Breasthooks and Stemson <u>Good</u>	Pumps
Comings <u>Good</u>	Transoms, Pointers, and Crutches <u>Good</u>	Boats
Upper Deck Beams & Fastenings <u>Good</u>	Timbers of the Frame <u>good whereas</u>	Masts, Yards, &c. <u>Good</u>
Lower Deck Beams & Fastenings <u>Good</u>	Keelsons	Sails
Planksheers	Clamps and Shelves	Anchors No. of <u>Sufficient</u>
Sheerstrakes	Ceiling <u>Good</u>	Cables
Topsides <u>Good</u>	Rudder	Hawsers and Warps
Wales	Copper <u>4 1/2</u> When put on <u>1852</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

We are of opinion this vessel is in good condition to continue as classed

The Amount of Fee £ _____ is received by me,

Damage Special 3: 3: 0th
 each Attendance 1: 1: 0th
 Certificate (if required) : 5: -

Committee's Minute 28th Jan^y 1852

Character assigned 12 A1



© 2019

Lloyd's Register Foundation

LON631-0241