

REPORT of SURVEY for REPAIRS.

17312

No. 84 Survey held at London Date Jan 21 to 29 1852
 on the Brig Adelaide Master C. Gornier Brett
 Tonnage 250 Built at Dundee When built 1831
 By whom built London Owners Messrs F. W. Tennant
 Port belonging to Hobart Town Destined Voyage Hobart Town Tobago
 If Surveyed Afloat or in Dry Dock In Dawson's Dry Dock

Last Survey, No. 14332 Port London Classed D. S. 49

REPAIRS at the present time of damage sustained by grounding at the mouth of the Thames in her passage to London; more of particulars in Special Report.

Yellow Metal Sheathing stripped off the Bottom, and renewed upon Felt; hung in shores, Caulked from Wales to keel, chafed Bilge Planks rubbed over, a Plank of Ceiling removed at Starb^d Bilge to ascertain the condition of the Timbers there, and found them in good condition; the Plank replaced with new, about one inch trimmed off underside of main keel all fore and aft, it being chafed, and a new False keel introduced 4ⁱⁿ thick, split after end of main keel secured by two Stirrup Straps of Yellow Metal not of damage. The Planks here, ^{Wales Topsides} and Waterway Seams Caulked

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>Good</u>	Breasthooks and Stenson } <u>Good where seen</u>	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. } <u>In good order</u>
Lower Deck Beams & Fastenings } <u>d^r where seen</u>	Keelsons } <u>d^r</u>	Sails } <u>and sufficient</u>
Plank sheers	Clamps and Shelves } <u>d^r</u>	Anchors No. of
Sheerstrakes } <u>d^r</u>	Ceiling } <u>d^r</u>	Cables
Topsides } <u>d^r</u>	Rudder } <u>d^r</u>	Hawsers and Warps
Wales } <u>d^r</u>	Copper } <u>When put on now new</u>	Standing & Running Rigging
Plank (Bottom) and Counter } <u>d^r</u>		

General Observations and Opinion,

This Brig now appears fit for the safe conveyance of dry and perishable cargoes "to and from all parts of the world" eligible to remain as classed *A

The Amount of Fee.....£ 1 : : is received by me,

Special..... 2 : 2 : -

Certificate (if required) : 10 : -

Committee's Minute

Character assigned

Special Report } £ 2.2.0
 or damage