

REPORT of SURVEY for REPAIRS.

17388

No. 596 Survey held at London Date Dec 11 / 14 March 1852
 on the Bk Commodore Master W. Hove
 Tonnage 203 Built at Newport When built 1835
 By whom built _____ Owners Shepherd & Co
 Port belonging to London Destined Voyage Tobago
 If Surveyed Afloat or in Dry Dock Youngs Dock

Per 3rd March

Last Survey, No. 10857 Port London Classed 12 A
C 4 6

REPAIRS No shake at the tight water mark taken out fore aft on both sides
and a listing cat out inside below the hold beams, found all the
timbers sound, a five inch stroke has ^{been} wrought of teak where opened
& nine shakes of doubling up to the Black Shakes, four upper shakes
of teak & five of American Elm, through fastened with treenails
a through bolt at the bulk & every ten feet, all the bolts in the iron
staple & iron knees & throat bolts of the iron hanging, through
the doubling, scraped bright & bolts & treenails out & found in good
condition, the water ways planks, keels, beams, hawse timbers
knight head, breasthooks, transoms, floors & keelsons, planking
outside & ceiling are all in sound state, the keel is straight
& has preserved her original form - bottom caulked & sheathed
with yellow metal on felt

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper <u>Wm</u> When put on <u>1852</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

We are of opinion this vessel is in good condition for
the safe conveyance of dry & perishable cargoes to
& from all parts of the world and may be classed
A1 with the distinction of the Atlantic

The Amount of Fee.....£ 1 : : is received by me,


Special..... 3 : 3 : -

Certificate (if required) : :

Committee's Minute 19 March 1852

Character assigned A1

R. J. M. Stetson
J. H. Ritchie



Lloyd's Register
 Foundation
 LON631-0346