

REPORT of SURVEY for REPAIRS.

No. 11 Survey held at London Date Feb 26 to March 1852
 on the Ship "Walmer Castle" Master Atkinson W B Price
 Tonnage 656 Built at London When built 1836
 By whom built _____ Owners R Green
 Port belonging to London Destined Voyage Calcutta
 If Surveyed Afloat or in Dry Dock In Mess^r Green's lower Dry Dock

Last Survey, No. 10578 Port London Classed 12 A 1

REPAIRS at the present time under Special Survey Rule for Restoration Sec No 55.56
 All the Bolts in the range of each Deck driven out, and the Planks taken out,
 the upper Deck Waterway, Plank sheer, and Spiketting, a Stake next the Waterway
 on the Lower Deck, a Stake of Bottom between Wale and light water mark
 and a Plank of Ceiling at Floor Heads on each side removed, the yellow
 metal sheathing entirely stripped off the Bottom and the ship thoroughly
 exposed to view which led to the following Repair, which are new
 viz Both Sheer Stakes of African Oak 4ⁱⁿ thick, three Stakes of Topsides
 Pitch Pine, two Black Stakes Pitch Pine, six Stakes of Wale African
 Oak 6ⁱⁿ thick, the 5th Stake of Bottom below Wale English Oak, one Stake
 of Bottom next below Wale Stake and two on the Port side, 15 after Head
 in Buttock Stake and 10 on the Port side new all of English Oak, all outside
 Planking of Forecastle new of English Oak, Plank sheer in Waist and Forecastle
 of African Oak, and of Poop Pitch Pine, Planking in upper course of Bottom
 dubbed bright, upper Deck Waterway new of African Oak, Spiketting Pitch Pine, masts
 all inside bulwark of Forecastle new, 10 Dougal Piers bulwark ends of upper Deck
 Present Condition of the
 Decks part new
 Waterway Upper Deck new } good
 Comings _____
 Upper Deck Beams & Fastenings Bolts all new } d^o
 Lower Deck Beams & Fastenings } d^o
 Plank sheers new d^o
 Sheerstrakes new d^o
 Topsides new d^o
 Wale new d^o
 Plank (Bottom) and Counter d^o

Treenails pt new
 Breasthooks and Stemson _____
 Transoms, Pointers, and Crutches } good where
 Timbers of the Frame pt new } good where
 Keelsons _____ d^o
 Clamps and Shelves _____ d^o
 Ceiling _____ d^o
 Rudder _____ d^o
 Copper metal } When put on new new
 Windlass and Capstan _____
 Pumps _____
 Boats _____
 Masts, Yards, &c. _____ In good order
 Sails _____ and sufficient
 Anchors No. of _____
 Cables _____
 Hawser and Warps _____
 Standing & Running Rigging stripped

General Observations and Opinion,

This Ship has now been "Specially Surveyed" in accordance
 with Rule Sec No 55.56, and very heavily repaired for Restoration
 We are of opinion that she is in good condition fit for the safe conveyance
 of dry and perishable Cargoes to and from all parts of the world
 The Amount of Fee.....£ 5 : - : - is received by me,

Special..... 10 : 10 : -

Certificate (if required) : 10 : -

Committee's Minute 30 March 1852

Character assigned Restored A 1

Special Restoration
 Fee £ 10-10-0

Lloyd's Register
 Foundation

LON631-0370

17412 Lon
Repairs continued.

All Bolts of Lower Deck now of Yellow Metal new and those above of Iron, three Planks of Ceiling between 2^d new of Pitch Pine, new Arms to two Upper Deck Beams, 10 feet of Upper Deck Plank new. The following Timbers of the Frame are new of English Oak Starboard side 15 Long Top Timbers extending down to 2^d Buttress Heads, 34 Short Top Timbers, 14 Rough tree Stantion, or Poop and Forecastle, and all of those in the Waist; Port side 16 Long Top Timbers extending down to the 2^d Buttress heads, 39 Short Top Timbers, 16 Rough tree Stantion, or Poop and Forecastle and all those in the Waist, and the Knight head, the last named is of African Oak. Both Side Counter Timbers and two Transoms new of English Oak, hung in show, Caulked throughout and the Bottom resheathed with Yellow Metal or Felt, those Treennails which remained in have been all tried by Caulkers, Knee of Head stripped and most of its fittings new. Rudder Booms all off and refitted. The remaining portion of original Inside and outside Planking, Treennails, Beams, Shelf pieces, Hooks, Keelson, Keel, Transoms Floors and Timbers of the Frame have been examined ~~where~~ they may be seen and appear to be in good condition. Planking of Lower Counter new.

J. S. Martin



© 2019

Lloyd's Register
Foundation