

17425

REPORT of SURVEY for REPAIRS.

Continuation

No. 690 on the Sch. "Susan" Survey held at London Date 18 Feb 1852
Tonnage 190 Built at Cowes Master Collings
By whom built Collings Owners Collings
Port belonging to London Destined Voyage
If Surveyed Afloat or in Dry Dock on West's ways

Last Survey, No. 1577 Port London Classed 12 A Nov E.

REPAIRS at Present keels, topsides, and sheer strakes and plank sheers & waterways scraped bright one length of sheer strake renewed on both sides and ships of English oak treenails good and bolts where wasted renewed in the shelf - the keelson being found defective at the middle scarp a double scarp piece with 6" hog over it has been fitted the upper deck & coming - the outside & ceiling, plank the plank sheers waterway, beams the hauser timbers knightheads, breasthooks & transoms the floors and keelson and the frame & inner surface of the outside plank where seen are sound & good & the sheer and general form unaltered -

Present Condition of the			
Decks	Good	Treenails	Good
Waterways	Caulked	Breasthooks and Stemson	Good
Comings	in & out both renewed	Transoms, Pointers, and Crutches	Good
Upper Deck Beams & Fastenings	Good	Timbers of the Frame	Good
Lower Deck Beams & Fastenings	Good	Keelsons	Good
Plank sheers	scraped	Clamps and Shelves	Good
Sheerstrakes	bright	Ceiling	Good
Topsides	Good	Rudder	Good
Wales	Good	Copper	Yarn When put on 1849
Plank (Bottom) and Counter	Good		
		Windlass and Capstan	Good
		Pumps	Good
		Boats	two
		Masts, Yards, &c.	sufficient
		Sails	D
		Anchors No. of	3 1 1
		Cables	sufficient
		Hawsers and Warps	D
		Standing & Running Rigging	D

General Observations and Opinion, This vessel is in efficient Condition and all the requisites of rules Sect 54 have been complied with she is eligible to be Continued

The Amount of Fee.....£ 2 : - : - is received by me, on the first Clasp for the longest period

Special..... 3 : 3 : -

Certificate (if required) : : :

Committee's Minute 6 April 1852

Character assigned in P A 1 for 4 days 1851

Prescribed by the rules say from 1857. 47th A.D.

