

REPORT of SURVEY for REPAIRS.

Continuation and Change of Owners

No. 357 Survey held at London Date 15 till 23 June 1852
 on the B^{re} "Himalaya" Master Sangford
 Tonnage 403 Built at Sunderland When built 1840
 By whom built — Owners G Marshall
 Port belonging to London Destined Voyage St Phillip
 If Surveyed Afloat or in Dry Dock in Sunderland Dock & afloat
N. Klen & S. prs 49

Last Survey, No. 15252 Port London Classed 10 R. N. expunged

REPAIRS at present bottom stripped Caulked & washed with
 yellow Metal on felt - Wales, topsides, & Sheerstrakes
 scraped bright and bolts and treenails driven
 out for survey and found sound & good -
 the timber strakes thro' bottom with yellow Metal
 Ceiling repaired one pair of Iron Standard Run
 fitted on the after hold beam all new hold & twist
 deck planks fitted head rail bolting & facing
 renewed - Part new upper deck and all ^{galleys}
 new main mast shipped and rigging overhauled
 and refitted - The deck & Comings the bottom
 and Ceiling planks the plank sheers waterways and

Present Condition of the		and Ceiling planks the plank sheers waterways and	
Decks	Partly new Good	Treenails	Good
Waterways	—	Breasthooks and Stenson	—
Comings	—	Transoms, Pointers, and Crutches	—
Upper Deck Beams & Fastenings	—	Timbers of the Frame	—
Lower Deck Beams & Fastenings	—	Keelsons	New 1849 —
Plank sheers	—	Clamps and Shelves	—
Sheerstrakes	Scraped	Ceiling	Repaired —
Topsides	bright	Rudder	—
Wales	Good	Copper	Ym When put on June 1852
Plank (Bottom) and Counter	—	Windlass and Capstan	Good
		Pumps	—
		Boats	New main mast
		Masts, Yards, &c.	—
		Sails	2 sheets
		Anchors	No. of 3 1 1
		Cables	Sufficient
		Hawsers and Warps	—
		Standing & Running Rigging	—

General Observations and Opinion,

This Vessel is in efficient Condition and
 in our opinion eligible to be Continued on the
 first Class for the longest Period Prescribed by the

The Amount of Fee.....£ 5 : — : — is received by me, Rules say from 1850

Special..... 3 : 3 : —

Certificate (if required) — : 10 : —

Committee's Minute 25 June 1852

Character assigned

1st A 1 or 3 yrs
1850 - 1853
1850 - 1853

17589 Lon

and beams the main timbers, Keelhead, breasthooks
and transoms the floors & bulkheads and the plating
and inner surface of the outside planks wherever
are sound & good and the sheer and general form see
attached and all the requisites of Rules Sect. 54, Complied
with

J. H. Ritchie

J. H. Ritchie
J. H. Ritchie