

REPORT of SURVEY for REPAIRS.

17596
J. Martin

No. 364 Survey held at London Date May 20 to June 24 1852
 on the Ship "True Briton" Master M Beatts
 Tonnage 506 Built at London When built 1835
 By whom built _____ Owners Messrs Wigram & Co
 Port belonging to London Destined Voyage New Zealand
 If Surveyed Afloat or in Dry Dock In Messrs Wigram & Co's Dry Dock

Last Survey, No. 10738 Port London Classed 12 A 1
 Cont 47 4 51

REPAIRS at the present time under Special Survey Rule for Restoration Sec Nos 55, 56. All the Bolts in the range of each Deck driven out, and the Outside Planking thro' which they passed removed, the upper Decks Waterway, Planksheer, and a Stake of Bottom betwixt Wales and light water mark removed on each side, a disting of Lower Decks cut out all fore and aft each side next the Waterway and the Beams in way of it well examined, the Yellow Metal Sheathing stripped off the Bottom, the Planking brightened from light water mark upward, Treanails driven out at various parts for examination and a Plank of Ceiling lifted at Floor Heads on each side, the Timbers in thoroughly examined which led to the following Repair with new and suitable materials. Four upper Stakes of Wale new of Sibiric and Pitch Pine; two Black Stakes of Dantzic Oak and Pitch Pine; two Stakes of Topside Pitch Pine, both sheer Stakes of Dantzic Oak, four upper Stakes abreast of Poop, and about half the Outside Planking abreast of Deck betwixt Posts, also the whole of Outside Planking around the Forecastle of Dantzic Oak; 4th Stake of Bottom below Wales of Dantzic Oak; upper and lower Counter new; side Counter Timber on the Outside

Decks	Treanails	Windlass and Capstan
Waterways } <u>Good</u>	Breasthooks and Stenson	Pumps
Comings } <u>Good</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings } <u>d^o</u>	Keelsons	Sails
Planksheers new	Clamps and Shelves	Anchors No. of
Sheerstrakes <u>d^o</u>	Ceiling	Cables
Topside <u>d^o</u>	Rudder	Hawsers and Warps
Wales <u>pt d^o</u>	Copper Metal	Standing & Running Rigging
Plank (Bottom) and Counter <u>d^o</u>	Don Felt	

General Observations and Opinion.
 This Ship has now been "Specially Surveyed" and repaired in conformity with Rule for Restoration Sec Nos 55, 56 and we are of opinion that she is in good condition fit for the safe conveyance of Dry and perishable Cargoes to and from all parts of the world eligible to be visited.

The Amount of Fee.....£ 5 : - : - is received by me,
 Special..... 10 : 10 : -
 Certificate (if required) : 10 : -
 Committee's Minute 1 July 1852
 Character assigned Restored

Special Repair } £10-10-0
 Restoration }
 J. Martin
 Lloyd's Register Foundation
 LON 632-0046

17596 Lon

Repairs Poop-Jar?

32 Rough-tree Stantions, 21 Short Top Timbers, & 23
Fillings in wide spaces, on each side all of English
Oak, Upper piece of Stem, upper piece of Apron,
and the Knight Head on the Port side new of English
Oak; Plank here of Dantzic Oak, Upper Deck, Waterway
of Baltic Red Pine; 54 feet of Main Keelson in Face
Body of East India Teak, the Deadwood at Star side
of Foremost Floor & Plank here on Poop and Forecath
of Dantzic Oak new; Knee of Head, and all belonging
to it new. Lower Deck Bolts renewed with Yellow Metal,
and those of Upper Deck with Iron. Ceiling in
Hold Dressed over, refastened where necessary, and about
700 feet of it new. Ceiling between Decks scraped
bright and examined, about $\frac{3}{4}$ of Upper Deck new, ^{and Iron fastened,}
Ship Caulked throughout, and the Bottom Sheathed
with Yellow Metal on Felt; fourteen angular Chocks at
Floor and Post Butt-heads amidship new; Channels off, and repair
all Chain Bolts new.

The Deck, Coamings, Upper and Lower Deck Bolts,
inside, and outside Planking; Treennails, Plank here
Waterway, Beams, Knees, Hooks, Knight heads, Hawse
Timbers, Keel, Keelson, Transoms, Floors and
Timbers of the Frame where they may be seen, have
been examined, and are in good condition.

JM



© 2019

Lloyd's Register
Foundation