

# REPORT of SURVEY for REPAIRS.

No. 17609 Survey held at London Date June 23 to 30 1852  
 on the B<sup>e</sup> Josephine Master J Harrison  
 Tonnage 279 Built at Wokington When built 1839  
 By whom built \_\_\_\_\_ Owners J Harrison  
 Port belonging to London Destined Voyage Columbo River  
 If Surveyed Afloat or in Dry Dock In Mess<sup>r</sup> Dawson & Co Dry Dock

Last Survey, No. 14,033 Port London Classed 12 A 40 Ship omitted

## REPAIRS

Now done under "Special Survey" Rule Sec R<sup>e</sup> 54

The outside Planking from lower part of Wales upwards scraped bright, Treennails and Iron Bolts driven out at various parts for examination, Yellow Metal Sheathing stripped off the Bottom and renewed upon Felt Aloft and Paper below, Caulked from Keel to Gunwales, all Treennails from light water marks upwards tried by the Caulkers. A defective Timber, which crossed the Stern below Hold Beams replaced; and Chocks driven into air course to support Butts of Clamp and Ceiling

The Deck, Coamings, Deck and Hold Beam Bolts, inside and outside Planking, Treennails, Watertight, Planksheer, Beams, Knives, Hooks, Knight heads, Hamsie Timber, Transoms, Keel, Keelson, Floors and Timbers of the Frame where they may be seen have been examined by us and appear to be in good condition.

Decks	Treennails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper	Standing & Running Rigging
Plank (Bottom) and Counter	When put on <u>now near</u>	

## General Observations and Opinion,

This B<sup>e</sup> has now been "Specially Surveyed" by us in conformity with Rule Sec R<sup>e</sup> 54, and we are of opinion that she is in good condition, eligible to re-class A, Cont. 4 years from 1850

The Amount of Fee.....£ 3 : — : — is received by me,

Special..... 3 : 3 : —

Certificate (if required) : 10 : —

Committee's Minute

Character assigned

Special Fee on Continuation { £ 3-3-0