

REPORT of SURVEY for REPAIRS.

Re Entry for Asterisk

No. Survey held at London Date May 13 to June 1852

on the Bg Botivar Master

Tonnage 204 Built at Whitchurch When built 1824

By whom built Owners Grathend

Port belonging to London Destined Voyage St Vincents

If Surveyed Afloat or in Dry Dock Simkirk Dock

ND & Sips 49

Last Survey, No. 15885 Port London Classed 11 *E on 11th

REPAIRS *At the present time all the keeneails renewed from the bilge to the Sheerstrakes about 6500, the bolts of the shelves and throat bolts of the hanging knees renewed, a crutch & dead wood knee aft new upper upper piece of apron, knight heads, hawse timbers, two breasthooks, two lower iron breasthooks rebolted, two catheads, two new cast timbers, thirteen rough keel sections head rebolted, caulked from the keel overall & sheathed with Yellow Metal on felt,*

Has been scraped bright, and found the the deck, comings, plank sheer waterways, beams, hawse timbers, knight heads, breasthooks, transoms floors & keelsons, planking outside & inside are all in a sound state & her sheer appears to have preserved its original form—

Present Condition of the

Decks	Treenails <u>new</u>	Windlass and Capstan <u>good</u>
Waterways	Breasthooks and Stenson <u>good</u>	Pumps <u>D^o</u>
Comings	Transoms, Pointers, and Crutches <u>D^o</u>	Boats <u>D^o</u>
Upper Deck Beams & Fastenings	Timbers of the Frame <u>good when seen</u>	Masts, Yards, &c. <u>D^o</u>
Lower Deck Beams & Fastenings	Keelsons <u>D^o</u>	Sails <u>well found</u>
Plank sheers	Clamps and Shelves <u>D^o</u>	Anchors No. of <u>3 Bows Stream & Kedge</u>
Sheerstrakes	Ceiling <u>D^o</u>	Cables <u>well found</u>
Topsides	Rudder <u>D</u>	Hawsers and Warps <u>D^o</u>
Wales	Copper <u>Yellow Metal</u> When put on <u>1852</u>	Standing & Running Rigging <u>good</u>
Plank (Bottom) and Counter		

General Observations and Opinion *This vessel has complied with the rule Sect 54 & 60 and we are of opinion she is fit for the safe conveyance of dry & perishable cargoes to & from all parts of the world and may be classed E, 1 with the Asterisk*

The Amount of Fee.....£ 4 : : is received by me,

Special..... 3 : 3 : —

Certificate (if required)

Committee's Minute 24 Aug 1852

Character assigned

Special Survey Fee £3-3-0