

REPORT of SURVEY for REPAIRS.

Continuation

No. *33* Survey held at *London* Date *August 24th Sep^r 1852*

on the *By Wanderer* Master *N. Glendinning*

Tonnage *173* Built at *Prince Edward Island* When built *1847*

By whom built _____ Owners *Glendinning & Co*

Port belonging to *Cape Town* Destined Voyage *Cape of Good Hope*

If Surveyed Afloat or in Dry Dock *Dry Dock & Ways*

Last Survey, No. *14,825* Port *London* Classed *4 A 1 Expunged*

REPAIRS, *new fore piece of keel 24 feet, new fore piece of keelson 14 feet & rider over it, new false stem post, one new rudder brace, 152 feet of new oak sheer stake 94 feet of new topsides, 146 feet of new ceiling, 115 feet of new deck next waterway, 270 new keenails, caulked from the keel overall & sheathed with yellow metal on paper*
Has had a stake taken out at the turn of the bilge fore & aft on both sides fore & aft, also a stake in the topsides removed fore & aft & found in good condition as well as the bolts & keenails which have been driven out, the plank sheer, waterways, beams, hawse timbers, knight head, breasthooks, & transoms, floors & keelsons, planking outside & inside are all in a good condition

Present Condition of the

| | | |
|-------------------------------|---|----------------------------|
| Decks | Treenails | Windlass and Capstan |
| Waterways | Breasthooks and Stenson | Pumps |
| Comings | Transoms, Pointers, and Crutches | Boats |
| Upper Deck Beams & Fastenings | Timbers of the Frame | Masts, Yards, &c. |
| Lower Deck Beams & Fastenings | Keelsons | Sails |
| Plank sheers | Clamps and Shells | Anchors No. of |
| Sheerstrakes | Ceiling | Cables |
| Topsides | Rudder | Hawsers and Warps |
| Wales | Copper <i>4 1/2</i> When put on <i>4052</i> | Standing & Running Rigging |
| Plank (Bottom) and Counter | | |

General Observations and Opinion, *This vessel has complied with the rule Sect 54 & 63 & we are of opinion she may be continued two years A 1 from 1851 & marked S S for years —*

The Amount of Fee.....£ 2 : — : — is received by me,

Special.....3 : 3 : —
 Certificate (if required) : 5 : —

Committee's Minute *17 Sept 1852*

Character assigned *Cont A 1 for 2 Years from 1851*

Record repair S.S. 1852