

17807

REPORT of SURVEY for REPAIRS.

Special Historic

Rec 13<sup>th</sup> Oct

No. 209 on the Survey held at London Date 22<sup>nd</sup> Dec<sup>r</sup> 1852  
Br<sup>s</sup> Thomas & Joseph Cripp Master J Williams

Tonnage 319 Built at Sunderland When built 1840

By whom built \_\_\_\_\_ Owners Cum gratia

Port belonging to London Destined Voyage Lancaster

If Surveyed Afloat or in Dry Dock at first in Dowlson Slip & afterwards in ground

Last Survey, No. 11842 Port London Classed 8 R.

REPAIRS

at present one length of Sheerstrake renewed on each side from defects and one strake of topsides on both sides forward & aft removed to ascertain the Condition of the timbers of frame which were found generally sound - The topside and Sheerstrake and Plank Sheers have now been doubled ~~the topsides~~ with 2" dautye fir, the Sheerstrakes and Plank Sheer with 2" dautye oak all on felt <sup>thus better</sup> - The two upper throat bolts that is the lug & the throat bolts of the iron hanging knees renewed thro' the doubling - Wale & black strokes scraped bright and bolts and bunails drawn out for survey aged found sound & good - all the quantity of sec<sup>rs</sup> 40 Complied with metal patches

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shells	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper <u>Ym</u> When put on <u>1850</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

This Vessel is now in efficient Condition and in our opinion fit for the safe conveyance of dry and perishable Cargoes to & from all parts of the world and eligible to be Clapped

The Amount of Fee £ 2 : - : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) : 10 : -

Committee's Minute 14 Dec 1852

Character assigned 1st

J. A. Ritchie  
Lloyd's Register  
Foundation