

# REPORT of SURVEY for REPAIRS.

17954

No. 176 Survey held at London Date 10<sup>th</sup> 27<sup>th</sup> Dec<sup>r</sup> 1852  
 on the Ship "Symmetry" Master Richardson  
 Tonnage 382 Built at Scarbro When built 1823  
 By whom built \_\_\_\_\_ Owners W. Tindall  
 Port belonging to London Destined Voyage Robert town  
 If Surveyed Afloat or in Dry Dock in Mr Tindalls Dock

Last Survey, No. 14889 Port London Rest. 10 y<sup>rs</sup> C. 2 55 1850  
 Classified \*A1

## REPAIRS

at Present all the old flat of the upper deck removed except the after lengths under the props and 8 new upper deck beams fitted of Iron bark and new deck of 3" yellow pine laid down with Copper nails a listing cut from the ends of the stay doubling under the wales and the beam under Caulked the lower deck shelf bolts new of yellow metal two new pumps fitted with new thick stuff bands pumps & throats on deck of Iron bark - yellow metal sheathing repaired -

## Present Condition of the

Decks <u>New</u>	Treenails	Windlass and Capstan <u>Good</u>
Waterways <u>Good</u>	Breasthooks and Stenson	Pumps <u>two new</u>
Comings <u>new beam port</u>	Transoms, Pointers, and Crutches	Boats <u>4 good</u>
Upper Deck Beams & Fastenings <u>shipped and fitted</u>	Timbers of the Frame	Masts, Yards, &c. <u>sufficient</u>
Lower Deck Beams & Fastenings <u>Good</u>	Keelsons <u>Good</u>	Sails <u>2 sets</u>
Planksheers	Clamps and Shelves	Anchors No. of <u>4 - 1 1</u>
Sheerstrakes	Ceiling	Cables <u>90 fath. 1 1/2 new</u>
Topsides	Rudder	Hawsers and Warps <u>sufficient</u>
Wales <u>Caulked</u>	Copper <u>Ym</u> When put on <u>1851</u>	Standing & Running Rigging <u>do</u>
Plank (Bottom) and Counter		

## General Observations and Opinion,

This Vessel is in efficient Condition and fit for the safe conveyance of dry and perishable Cargoes to & from all parts of the world and fit to remain as Classed

The Amount of Fee.....£ 2..... is received by me,

Special.....


Certificate (if required) : 10 : -

Committee's Minute

Character assigned

W. with asterisk

I. H. Ritchie



© 2019

Lloyd's Register Foundation

LON 632-0412