

18046

# REPORT of SURVEY for REPAIRS.

No. 126 on the *B<sup>k</sup> Pearl* Survey held at *London* Date *Feb<sup>y</sup> 11 to 17* 1853  
Master *Langford Orchard*  
Tonnage *361* Built at *Sunderland* When built *1842*  
By whom built \_\_\_\_\_ Owners *Gollinson & Co*  
Port belonging to *London* Destined Voyage *Montreal*  
If Surveyed Afloat or in Dry Dock *Dry in Fountain Shipway*

Last Survey, No. *17311* Port *London* Classed *10 Dec 1*  
*3 mo 52*

## REPAIRS

Now done in conformity with Special Survey Rule for Continuation Sec R<sup>o</sup> 54. The Outside Planking from Y. M. Sheathing upwards scraped bright, Treennails and Box Bolts driven out for examination at various parts:  
The Limber stake on each side, now thro' Bolted with Yellow Metal at every Floor, all Treennails tied by the Caulkers in the two Black Stakes, and four upper stakes of Wales, and about 200 of them replaced with new, the space between this and the Yellow Metal Sheathing (viz five stakes) had the Treennails renewed in July last. A Short Plank in the Port Buttock new, and a thro' piece on the Starb<sup>d</sup> side; the three lower breadths of Sheathing (for the protection of Planking from Ice) at each Bow stripped off and renewed, the other three breadths were renewed last Feb<sup>y</sup> under the survey of Mess<sup>rs</sup> Coutinay & Ritchie  
Present Condition of the

Decks	Treennails	Windlass and Capstan
Waterways } <i>Good</i>	Breasthooks and Stenson	Pumps
Comings } <i>Good where seen</i>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <i>In good order</i>
Lower Deck Beams & Fastenings } <i>d<sup>o</sup> where seen</i>	Keelsons <i>d<sup>o</sup></i>	Sails <i>and sufficient</i>
Planksheers	Clamps and Shelves <i>d<sup>o</sup></i>	Anchors No. of <i>3</i> <i>SIK 2</i>
Sheerstrakes <i>d<sup>o</sup></i>	Ceiling <i>d<sup>o</sup></i>	Cables
Topsides <i>d<sup>o</sup></i>	Rudder <i>d<sup>o</sup></i>	Hawsers and Warps
Wales <i>d<sup>o</sup></i>	Copper <i>of Metal</i> When put on <i>1852</i>	Standing & Running Rigging
Plank (Bottom) and Counter <i>d<sup>o</sup></i>		

General Observations and Opinion, *The Deck, Coamings, inside and outside Planking, Trussing Planksheer, Waterway, Beams, knees, Hooks, Knight Heads, Hanks, Timbers, Keel, Keelson, Floors and Timbers of the Frame where they may be seen have been examined by us and appear in good condition*

*We are of opinion that she is eligible to be Continued A 1 for three years from 1852 in accordance with Rule Section R<sup>o</sup> 54*

The Amount of Fee.....£ 4 : - : is received by me,

Special..... 3 : 3 : *18/2/53*

Certificate (if required) : - :

Committee's Minute *22<sup>nd</sup> July 1853*

Character assigned *Crit P A 1 pr 3*

*Special Survey Fee £ 3-3-0*

*J. D. Martin*

*Lloyd's Register Foundation*  
LON 632-0504