

REPORT of SURVEY for REPAIRS.

damage & Change of Owners

No. 32 Survey held at London Date 12th April 1853
 on the Ship Julia Master James Baker
 Tonnage 1055 Built at Quebec When built 1852
 By whom built H. Dabord Owners C. Guzman
 Port belonging to London Destined Voyage New York
 If Surveyed Afloat or in Dry Dock in Mr. P. H. Hatcher's Yard at the end of the
Weymouth Dock

Last Survey, No. 32 Port Quebec Classed

REPAIRS at present from damage on her voyage home from Quebec - Start new rails and bulwarks 600 feet new upper deck an additional shelf of American Oak 9x5x16" has been fitted both to the upper and to the lower deck beams both thro the alternate timbers with 1 1/4" iron bolts - and the beams bolted down to the old & new shelves & clamps with 70 bolts of 1" diam. and a pair of iron tidies fitted to the stern frame and bolted to the there after - most upper deck beams & the keel caulked from the keel up over the decks. all the above was for repair of damage and the following

Present Condition of the	for Repair of Damage and the following	in Compliance with Sect. 62 of the Act
Decks <u>Caulked</u>	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemon	Pumps
Comings	Transoms, Pointers, and Crutches	Boats <u>four</u>
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>well</u>
Lower Deck Beams & Fastenings	Keelsons	Sails <u>found</u>
Planksheers	Clamps and Shelves	Anchors No. of <u>3</u> / <u>1</u>
Sheerstrakes <u>all</u>	Ceiling	Cables <u>sufficient</u>
Topsides <u>Caulked</u>	Rudder	Hawsers and Warps
Wales	Copper <u>yes</u> When put on <u>June 1853</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

This vessel is now in excellent condition and may be classed as recomended - ed in Mr. Menzies Report No. 32 - Say
 The Amount of Fee.....£ 3 : 2 : - is received by me, from 1852. 6/11 A 1

Special..... 3 : 3 : -

Certificate (if required).....

Committee's Minute

Character assigned

Special Damage by Fire & Theft

LON 633-0185

18247 Lon

9 Pairs of Vertical & 1 Pair of diagⁿ iron Cables
fitted in the hots thro' bolted with yellow metal
to the 12 feet waterline & iron bolts above
11 Pairs of iron hanging knees to hot beams
6 Pairs of standard knees and
16 Pairs iron hanging knees to upper deck
6 Pairs iron knees fitted to the poop beams
4 breast hooks of iron and one Crutch fitted
as new & such deck laid on the hot beams
and the bottom sheathed with yellow metal
on felt - and all the Requirements of
the Rules Complied with

J. H. Ritchie



© 2019

Lloyd's Register
Foundation