

18287

# REPORT of SURVEY for REPAIRS.

*Continuation*

No. *861* Survey held at *London* Date *10 May 1852* 18*53*  
 on the *"Br. Mercurian"* Master *Geo. J. Case*  
 Tonnage *573* Built at *London* When built *1842*  
 By whom built \_\_\_\_\_ Owners *Thos. J. Case*  
 Port belonging to *London* Destined Voyage *Ly. Geny*  
 If Surveyed Afloat or in Dry Dock *in Limekiln Dock*

Last Survey, No. *16613* Port *London* Classed *10 A.A.*

REPAIRS at present keels, topsides, and sheerstrakes scraped bright and bolts and brunnails driven out for survey and the rigging of set 54 Complied with brunnails good bolts of lower deck renewed in throats upper deck bolts good new four hoods of keels on both sides and the bolts of lower deck hook renewed of view these new four hoods - 6 new after hoods of keels and 2 of topsides on the larboard buttock and 3 after hoods keels and out topsides on the starboard buttock timbers and the transoms exposed sound - all new after hoods of the Ceiling in the hold one new timber and 2 new Chock and brunnails renewed three new Ceiling and Crutch refitted timber strakes three bolts with 1/8 yellow metal - all the

Present Condition of the old upper deck removed except the after timbers under the foremast P. S. Tower

Decks <i>new on Good</i>	Treenails <i>large &amp; Good</i>	Windlass and Copstan <i>Good</i>
Waterways <i>Do</i>	Breasthooks and Stenson <i>Do</i>	Pumps <i>Do</i>
Comings <i>Do</i>	Transoms, Pointers, and Crutches <i>Do</i>	Boats <i>Sufficient</i>
Upper Deck Beams & Fastenings <i>new bolts new girths</i>	Timbers of the Frame <i>Good</i>	Masts, Yards, &c. <i>Do</i>
Lower Deck Beams & Fastenings	Keelsons	Sails <i>Do</i>
Plank sheers	Clamps and Shelves	Anchors No. of <i>Do</i>
Sheerstrakes <i>scraped</i>	Ceiling <i>much new work</i>	Cables <i>Do</i>
Topsides <i>bright</i>	Rudder	Hawsers and Warps <i>Do</i>
Wales <i>good</i>	Copper <i>up</i> When put on <i>May 1853</i>	Standing & Running Rigging <i>Do</i>
Plank (Bottom) and Counter		

General Observations and Opinion.

*This vessel is now in efficient condition and eligible to be continued in the first class for the period prescribed by the Act of 1844 from*

The Amount of Fee.....£ *5* : - : - is received by me, *1852 34 years A.A.*

Special..... *3* : *3* : -

Certificate (if required).....

Committee's Minute *24 Jan 1853*

Character assigned *First A 1* is *3 years* *1852* *and up*  
*John Ritchie*  
*Lloyd's Register*  
*Foundation*  
*LOW 633-0225*

18287 Lon

Nine new upper deck beams fitted and all  
 new flat of deck 3" yellow pine laid except after hatches  
 under the Truss which are old but sufficient also  
 new 4" Sawtye pine planks of deck next water ways  
 were bolted — bottom stripped Caulked and  
 resheathed with yellow metal on felt —

J. H. Ritchie



© 2019

Lloyd's Register  
 Foundation