

REPORT of SURVEY for REPAIRS.

18318

No. 84 Survey held at London Date 15th 27th June 1843
 on the Ship Victoria Master Morrison
 Tonnage 666 Built at St. John's & Co When built 1840
 By whom built _____ Owners J. Shepherd
 Port belonging to London Destined Voyage Singapore
 If Surveyed Afloat or in Dry Dock Mess Wigrams dry dock

Last Survey, No. 1685 Port of London Classed 4 A 1
80.

REPAIRS At present, bottom stripped, hung, caulked, with yellow metal over felt. Knee of head, hause pipes, timbers, rails, chocks all new, opened above all round at topside the timbers exposed good. They have salt'd her fore & aft with fifteen Tons of salt, opened also at floor beams inside, found very good. Five new fore hoods on starboard bow 2 new do on port bow, one iron strap to connect the pointers aft. Saw lower masts fore chain & chaser with bowsprit, fore & chain lower yards new, fore & main topmasts new with jib boom, standing & running rigging all refitted.

present Condition of the

Decks <u>Good</u>	Treenails	Windlass and Capstan <u>Good</u>
Waterways <u>do</u>	Breasthooks and Stenson	Pumps <u>do</u>
Comings <u>do</u>	Transoms, Pointers, and Crutches	Boats <u>3ho do</u>
Upper Deck Beams & Fastenings <u>firm</u>	Timbers of the Frame	Masts, Yards, &c. <u>Good</u>
Lower Deck Beams & Fastenings <u>do</u>	Keelsons <u>caulked over & good</u>	Sails <u>2ho do</u>
Plankwalkers	Clamps and Shells	Anchors No. of <u>3 B 18 3 R</u>
Deerstrakes <u>scraped bright</u>	Ceiling	Cables <u>Left</u>
Topside <u>good</u>	Rudder <u>yellow over</u>	Hawesers and Warps <u>do</u>
Tales	Copper <u>boot top</u>	Standing & Running Rigging <u>do</u>
Hulk (Bottom) and Counter <u>Good</u>	When put on <u>June 1843</u>	

General Observations and Opinion, This vessel having complied with Sections 54 & 63. is now in efficient condition, and in our opinion is fit to be continued on the first class for the period prescribed, say from 1853 two years A 1 The Amount of Fee £ 5:- is received by me, N.S. 1853. 4 years.

Special..... 3 : 3 :

Certificate (if required) : 10:-

Committee's Minute 8th July 1843

Character assigned 4 A 1 in P D A 1 S B 4 M 1853

[Signature]

Wm D. Raper

LON633-0256

Lloyd's Register Foundation

18318 Son

Top-sides, sheer strakes, wales scraped bright, very good. Upper
or main decks and coverings, the upper and lower deck
bolts, and the outside planks and ceiling thro' which
they pass, the plank sheers, waterways, and beams,
house timbers, Rivingt nos, breasthooks & transoms;
the floors and Kelsons the Keel & ender; the plating
outside, and the frame and inner surface of the
outside plating where seen are sound and good.
Sheer & general form of the ship unaltered.

Charles Croker
J. H. Hatcher



© 2019

Lloyd's Register
Foundation