

REPORT of SURVEY for REPAIRS.

1839

No. 232. Survey held at London Date 12th July 18 53
 on the Ship Vava Master Robinson J. Robertson
 Tonnage 1175 Built at Calcutta When built 1813
 By whom built _____ Owners Somes Brothers
 Port belonging to London Destined Voyage India & Lagos
 If Surveyed Afloat or in Dry Dock Somes dry dock & E. India Docks
 E & d. 36 Dry Dock 50

Last Survey, No. 17082 Port London Classed *R/N Class
Ship hung N^o 50.

REPAIRS At present, bottom stripped, keel & main cantled
 & lister also wood ends, resheathed with yellow cedar
 over felt. The main or upper deck cantled, covered
 with felt, & covered with two inch plank deals from the
 poop to the bows fastened with By M. Spikes, new fore
 hatch cover - main hatch coverings & head ledge new,
 scupper taken out and refitted, spiketing cantled,
 partners round fore & main mast on upper deck new
 topgallant fore castle deck taken up four beams scupper
 with deck, two new beams of porridge white oak
 added to the after part & to lengthen the fore castle B.B.
Beams 10 x 4 & 8 x 7. P.T.O.

Present Condition of the			
Decks <u>doubled good</u>	Treenails	Windlass and Copstan	
Waterways <u>do</u>	Breasthooks and Stenson	Pumps	
Comings <u>do</u>	Transoms, Pointers, and Crutches	Boats	
Upper Deck Beams & Fastenings <u>in</u>	Timbers of the Frame	Masts, Yards, &c.	<u>Good &</u>
Lower Deck Beams & Fastenings <u>do</u>	Keelsons	Sails	<u>Left.</u>
Planksheers	Clamps and Shelves	Anchors No. of	
Sheerstrakes	Ceiling	Cables	
Topsides	Rudder	Hawsers and Warps	
Wales	Copper <u>gall.</u> When put on <u>Feb 1853</u>	Standing & Running Rigging	
Plank (Bottom) and Counter			

General Observations and Opinion, This vessel is in efficient condition and
in our opinion fit to remain as classed carry any
& perishable cargoes to & from all parts of the world.
I may be classed *A 1 as best.
 The Amount of Fee.....£ 3 : - : is received by me, Charles Corran

Special..... 1 : 1 : -

Certificate (if required) : 10 : -

Committee's Minute 2nd Aug 1853

Character assigned As best

Special L 1 1 recent repairs

LON 633-0334

REPORT of SURVEY for REPAIRS.

18395 *Len*

Henry X
 A new ^{Deck} of three inch ~~clau~~ deal, fastened with
 three ~~in~~ yellow metal spikes, guboard shake of
 doubling taken out fore & aft & put in new.
 The bottom caulked to copper line. — The upper part
 of false post taken off & refitted with new piece of ^{8 to 10} long
 same ~~thou~~ shiped at the wood ends. Two upper
 roller bands taken off & refitted over doubling
 plates new. A new rubber complete main
 piece E. Oak. Two new mast carlings put in the
 fore castle also part new in deck. 4 new pillars
 between decks and the upper deck set new before
 being double.

Charles Coker
A. H. L. Hines



© 2019

Lloyd's Register
 Foundation