

# REPORT of SURVEY for REPAIRS.

18414

No.        Survey held at London Date June 11<sup>th</sup> August 2<sup>nd</sup> 1853  
 on the "Bark Russian" Master Salata & Delataste  
 Tonnage 181 Built at Port When built 1831  
 By whom built        Owners Hargreaves & Co. & Jones  
 Port belonging to London Destined Voyage         
 If Surveyed Afloat or in Dry Dock Commercial dry dock

Last Survey, No. 1603 Port London Classed 12 R 40 Ship another       

## REPAIRS

At present bottom studded, ship hung, cant keel resheathed with yellow metal over felt. Scraped bright down to copper line, seventeen new timbers on Starboard side in the fore cant body, seven rough knees. English, Atlantic & African Oak materials. 6<sup>th</sup> of waterway Red Pine, 28<sup>th</sup> circular 14<sup>th</sup> of Atlantic pine. Sheerstrakes 168 ft 0 Red Pine, plank sheen 110<sup>th</sup> of English Oak. Males 7<sup>th</sup> 134<sup>th</sup> 0 of Eng Oak & 64<sup>th</sup> 0 of Red Pine, 90<sup>th</sup> 0 drift Oak, Deck & Deck tie 14<sup>th</sup> 0 Deck oak on bottom, Filling 440<sup>th</sup> 0 Red Pine & new Oak.

Starboard side. Timbers 15 No & 10 Rough knees, 93<sup>th</sup> 0 per waterways - sheerstrakes 136<sup>th</sup> 0, topsides 253<sup>th</sup> 0

## Present Condition of the

Decks <u>Good</u>	Treenails	Windlass and Capstan
Waterways <u>Do</u>	Breasthooks and Stenson	Pumps
Comings <u>Do</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings <u>Iron</u>	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings <u>Do</u>	Keelsons	Sails
Plank sheers	Clamps and Shelves	Anchors No. of 2-1
Sheerstrakes <u>Scraped</u>	Ceiling	Cables
Topsides <u>Scraped</u>	Rudder	Hawsers and Warps
Wales <u>Good</u>	Copper <u>Y M</u> When put on <u>1853</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

## General Observations and Opinion,

This vessel is in efficient condition, and fit to carry dry and perishable cargoes to & from all parts of the world. and in our opinion may be classed A 1 with asterisk & be marked 1853 1853.

The Amount of Fee.....£ 1 : - : is received by me,

Special..... 5 : 5 : -

Certificate (if required) : 5 : -

Committee's Minute

Character assigned

16<sup>th</sup> Aug 1853  
Special F 2 - 1853  
Charles Cooper  
A. H. Ritchie

LON 633-0353



18414. *Lan.*

plank sheers  $6\frac{1}{2}$  ft. 0 in., Malle  $9\frac{1}{2}$  ft. 0 in. bair &  $12\frac{1}{2}$  ft. 0 in. of Red Pine  
cleats 80 ft. 0 in., puttings  $4\frac{1}{2}$  ft. 0 in., Clamps & timber stocks  
 $10\frac{1}{2}$  ft. 0 in. One beam of E. Oak new Ekins, new apron  
and Stenson knee & chocks, 2 pieces of false keel,  
Isen winlass, one pair of hanging knees between decks  
four new iron breast hooks fastened with metal bol.  
one new iron crutch aft, new foremast, new forecrosse  
deck and a  $1\frac{1}{2}$  ft. 0 in. new on the main deck, and all  
the requisites of "Sect 60."

Charles Cooper

J. H. P. L. L.



© 2019

Lloyd's Register  
Foundation