

# 'Change of Owners' 1846

## REPORT of SURVEY for REPAIRS.

No. 36 Survey held at London Date 20<sup>th</sup> August 7<sup>th</sup> Sept 1853  
 on the Dr Herondelle Master R. Merrick  
 Tonnage 135 Built at Whitby When built 1835  
 By whom built          Owners Baker & Co  
 Port belonging to Dunder London Destined Voyage Melbourne  
 If Surveyed Afloat or in Dry Dock See Beam dock and London dock.

Last Survey, No. 1939 Port Dunder Classified 10<sup>th</sup> A<sup>1</sup> 1  
 REPAIRS N<sup>o</sup> 50 C 3.

At present, bottom stripped, caulked, resheathed with zinc over felt, two stakes of wales caulked, deck pieced, covering board midships found defective put in new with 3<sup>rd</sup> African Oak 27' 0" long also the <sup>plank sheers</sup> ~~port~~ repaired at the board of poop. 5 new roughed timbers. Lengthen sail from midships right aft 27' 0" long American Elm new, all new balustrade on the Starboard side the above repairs all on the Starboard side.

### Present Condition of the

Decks <u>good</u>	Treenails <u>        </u>	Windlass and Capstan <u>good</u>
Waterways <u>do</u>	Breasthooks and Stenson <u>good</u>	Pumps <u>do</u>
Comings <u>do</u>	Transoms, Pointers, and Crutches <u>do</u>	Boats <u>do</u>
Upper Deck Beams & Fastenings <u>fair</u>	Timbers of the Frame <u>wherever</u>	Masts, Yards, &c. <u>do</u>
Lower Deck Beams & Fastenings <u>do</u>	Keelsons <u>do</u>	Sails <u>do</u>
Plank sheers <u>do</u>	Clamp and Shelfs <u>do</u>	Anchors No. of <u>2 BLS 1 K</u>
Sheerstrakes <u>do</u>	Ceiling <u>do</u>	Cables <u>do</u>
Topsides <u>do</u>	Rudder <u>do</u>	Hawsers and Warps <u>do</u>
Wales <u>do</u>	Copper <u>zinc</u> When put on <u>1853</u>	Standing & Running Rigging <u>do</u>
Plank (Bottom) and Counter <u>do</u>		

### General Observations and Opinion,

This vessel is in efficient condition and in our opinion, may remain as classed A<sup>1</sup> 1 with red astute.

The Amount of Fee £ 10 - 10 - is received by me,

Special 1 - 1 -

Certificate (if required) : 5 -

Committee's Minute 9<sup>th</sup> Sept 1853

Character assigned A<sup>1</sup> 1