

18588

# REPORT of SURVEY for REPAIRS.

*Continuation*

1853 Nov

No. 438 on the *M. "Prospero"* Survey held at *London* Date *24<sup>th</sup>* *Oct.* 1853  
Master *Jay*  
Tonnage *117* Built at *Wienhoe* When built *1841*  
By whom built \_\_\_\_\_ Owners *Johnston*  
Port belonging to *London* Destined Voyage *N. Michals*  
If Surveyed Afloat or in Dry Dock *on Wests ways*

Last Survey, No. *14665* Port *London* Classed *12 A 1*

REPAIRS *at present wales topsides and Sheerstrakes scraped bright (but the planking from the wales to the light water line were not exposed from the reason stated in the accompanying letter from the Owner) - the trenails and bolts required were driven but for survey and all the other requirements of the Rules Sect 54 have been complied with - the Rudder bands have now been bolted and the yellow metal sheathing repaired -*  
*The upper deck & Comings the upper lower deck bolts the outside planks and Ceiling the bolt and trenails passing thro the same from the wales up*

Present Condition of the

Decks	<i>Good</i>	Trenails	<i>Good</i>	Windlass and Capstan	<i>Good</i>
Waterways	<i>Good</i>	Breasthooks and Stenson	<i>Good</i>	Pumps	<i>Good</i>
Comings	<i>Good</i>	Transoms, Pointers, and Crutches	<i>Good</i>	Boats	<i>two</i>
Upper Deck Beams & Fastenings	<i>Good</i>	Timbers of the Frame	<i>Good</i>	Masts, Yards, &c.	<i>Sufficient</i>
Lower Deck Beams & Fastenings	<i>Good</i>	Keelsons	<i>Good</i>	Sails	<i>2 Suits</i>
Planksheers	<i>scraped bright</i>	Clamps and Shells	<i>Good</i>	Anchors No. of	<i>3 . 1 . 3</i>
Sheerstrakes	<i>Good</i>	Ceiling	<i>Good</i>	Cables	<i>3 Chains</i>
Topsides	<i>Good</i>	Rudder	<i>bands repaired</i>	Hawsers and Warps	<i>7<sup>th</sup> 5<sup>th</sup></i>
Wales	<i>Good</i>	Copper	<i>Ym</i> When put on <i>Aug 1850</i>	Standing & Running Rigging	<i>Good</i>
Plank (Bottom) and Counter	<i>Good</i>				

General Observations and Opinion,

*This Vessel is in efficient Condition and in our opinion eligible to be continued on the first Class for the period prescribed by*

The Amount of Fee.....£ *2* : - : - is received by me, *the Rules say from 1853. 4 yrs A 1*

Special..... *3* : *3* : -

Certificate (if required) \_\_\_\_\_

Committee's Minute *4<sup>th</sup> Nov 1853*

Character assigned *12 A 1* *Cast. 4 A 1*  
*Charles Cooper*  
*Lloyd's Register*  
*Foundation*

NON634-0008



18588 Jan.

The Plank sheers waterways & beams the house  
timbers Knightheads brackthooks and transoms  
the floors & Kulsow the frame & inner surface  
of the outside Planks where seen are sound and  
good and the sheer and general form <sup>appear</sup> unaltered

J. A. Ritchie  
Charles, Esq.



© 2019

Lloyd's Register  
Foundation