

REPORT of SURVEY for REPAIRS.

Continuation

No. 12 Survey held at London Date 25th Jan^y 1854
 on the Ship "Femindar" Master J. S. Furber
 Tonnage 587 Built at Port Glasgow When built 1841
 By whom built _____ Owners Teighe & Co
 Port belonging to London Destined Voyage Australia
 If Surveyed Afloat or in Dry Dock in Mess^{rs} Bilbes Dock

18767

Re 1044

Last Survey, No. 17391 Port London Classed 12 A 1

REPAIRS at present bottom stripped wales, topsides and
 sheer strakes scraped bright and the bottom dubbed
 bright from the tight waterline to the wales and the
 following repairs done two new shafts of sheer strake
 in the bows done new shaft of topsides on the Starboard
 side three new afterhoods in larboard buttock all
 new in & out bolts of hole beam fastenings of yellow
 metal all new treenails from the floor heads up
 the two after lengths of Keelson new one of English
 oak the other of Teak the Stern post & after deck
 wood and the rudder additionally three bottles with
 yellow metal 480 feet new of the flat of upper deck
 P. Tower

Present Condition of the

Decks	480 ft new Caulked	Treenails	all new floors up	Windlass and Capstan	Good
Waterways	Good	Breasthooks and Stemson	Good	Pumps	Good
Comings	Good	Transoms, Pointers, and Crutches	new	Boats	Good
Upper Deck Beams & Fastenings	Good	Timbers of the Frame	Good	Masts, Yards, &c.	Sufficient
Lower Deck Beams & Fastenings	all in & out bolts new metal	Keelsons	new aft	Sails	Do
Planksheers	Scraped	Clamps and Shelves	Good	Anchors No. of	Do
Sheerstrakes	bright	Ceiling	Good	Cables	Do
Topsides	Good	Rudder	rebolted	Hawsers and Warps	Do
Wales	Good	Copper	Ym When put on Jan ^y 1854	Standing & Running Rigging	Do
Plank (Bottom) and Counter					

General Observations and Opinion,

This Vessel is now in efficient Condition
 and in our opinion eligible to be Continued on
 the first Class for the longest period prescribed

The Amount of Fee £ 5 : - : - is received by me, by the Rules say
 Special..... 3 : 3 : - from 1853. 4th Jan^y 1854

Certificate (if required) : 5 : -

Committee's Minute 14th Feb^y 1854

Character assigned Continued A 1

Special Damage £ 100

Charles R. Coker

© 2019 Lloyd's Register Foundation

634-0186

18767 Jan.

two new sets of Under bands and a new test fitted
both Nigger Channels new and one new Main ditto
hung in shores Caulked all over and bottom & sheathing
with yellow metal on felt — All the requisites
of Cables Sect^{ns} ^{have been} Complied with the upper deck
and Crossings the upper and lower deck bolts and the
outside and Ceiling Planks thro which they pass the
Plank sheers waterways and beams the house timbers
Kightheads breasthooks & transoms the floors & Mule
Kul & Under and the ^{frame and} inner surface of the outside Planks
where seen are sound & good and their line general
form unaltered —

J. H. Ritchie



© 2019

Lloyd's Register
Foundation