

REPORT of SURVEY for REPAIRS.

No. 647 Survey held at London Date 31th March 1854
 on the Barge "Molline" Master Stanbury
 Tonnage 440 Built at Sunderland When built 1834
 By whom built 573 Owners J. J. J. J.
 Port belonging to London Destined Voyage Coast Service
 If Surveyed Afloat or in Dry Dock Slitichers dry Dock

Last Survey, No. 17593 Port London Classed 11 1

REPAIRS

At the present time Sheerstrakes renewed with Dantzic Oak
 Six Buttresses plank on each side of Dantzic Oak, Three planks of
 Wale on Starboard Bow and two on Larboard Bow
 Fifteen planks of Grubbing on each Bow from Stem to Fore Rigg of Amn
 Elm, three Strakes of Forecastle berthing on the Starboard side and all
 new on the Larboard side of Pitch Line Upper and lower Deck fastenings
 Renewed Strengthened from Gunwale to low part of Wale, Channels
 renewed, two Stanchions to Poop new Brought in timbers the
 whole of the above repairs done with Dantzic Oak Pitch Pine and Oak
 The keel of head taken off and not replaced again, Poop Deck
 and Forecastle Deck Planked with Pine
 Ship hung on shores and Caulked from Keel upwards and Sheathed
 with Yellow Antelope over Felt

Present Condition of the

Decks <u>Good for Class</u>	Treenails <u>Good</u>	Windlass and Capstan
Waterways <u>Do</u>	Breasthooks and Stemson <u>Good for Class</u>	Pumps
Comings <u>Do</u>	Transoms, Pointers, and Crutches <u>Do</u>	Boats
Upper Deck Beams & Fastenings <u>Good</u>	Timbers of the Frame <u>Fair for Class</u>	Masts, Yards, &c.
Lower Deck Beams & Fastenings <u>Do</u>	Keelsons <u>Do</u>	Sails <u>Good & light</u>
Plank sheers <u>Do</u>	Clamps and Shelves <u>Do</u>	Anchors No. of <u>3 B&H</u>
Sheerstrakes <u>New</u> <u>Do</u>	Ceiling <u>Do</u>	Cables
Topsides <u>Do</u>	Rudder <u>Good</u>	Hawsers and Warps
Wales <u>Good for Class</u>	Copper <u>Y Metals</u> When put on <u>New</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

This vessel appears to be in a fair condition
 And fit for the conveyance of dry & perishable cargoes
 Eligible to remain Classed 11

The Amount of Fee.....£ 2 : - : - is received by me, J. M. M. J. J.

Special..... : :

Certificate (if required) : :

Committee's Minute 25th April 1854

Character assigned 11 Used upon 11



© 2019

Lloyd's Register
Foundation

104634-0355