

REPORT of SURVEY for REPAIRS.

19077
Recy line

No. 474 Survey held at London Date 13 May to 7 June 1854
 on the Ship Southampton Master R Roe
 Tonnage 908 Built at London When built 1841
 By whom built M. Migan Owners M. Migan
 Port belonging to London Destined Voyage Calcutta
 If Surveyed Afloat or in Dry Dock Miss Migan's Dry Dock & afloat

Last Survey, No. 14584 Port London Classed originally 12A1

REPAIRS Now done - Renewed about 70 ft fore part Main Keelson with Teak⁵² part Apron with Stems knee of 13" Oak - on Starboard side one short after Hood in Wales & one shaft in buttocks under Wales & two lining pieces all of 13" Oak Starboard side 3 after Hoods in Wales of 13" Oak Retenailed in round of Belgs with Gum Wood & 13" Oak - One additional Iron Hook applied under lower transom to secure heads of Cant-felling timbers two pair Iron Riders in way of Main Mast & 3 Iron (floor) Riders at Main & after Hatch all fastened with Yel Metal a few additional through bolts driven in Belgs of Yel Metal & also of Iron in Topsides - Caulked from Keel over all & sheathed with Yel Metal over felt

Survey for Continuation as per rule section 54 - Found the state of the Main deck & its appendages the upper & lower deck bolts & the planks through which they pass the Planksheers Waterways & Beams - Good House timbers Knight heads Breasthooks & Transoms - Sound - Floors - 3 in way of Keelson had partial defects cut out & gluing pieces inserted Keelson 2 fore lengths with Stems knee found defective were taken out Keel & Rudder outside planking (with the exception of pieces renewed) with the trenails passing through from the L.D. line were all good trenails in round of Belgs slightly wasted between plank & timber - the Ceiling inside frame timbers & inner surface of outside plank where seen were all in good order & condition

Present Condition of the


Decks	} <u>Good</u>	Treenails	<u>Good</u>	Windlass and Capstan	<u>D. W^h</u>
Waterways		Breasthooks and Stems		Pumps	<u>2</u>
Comings	} <u>Good & Firm</u>	Transoms, Pointers, and Crutches		Boats	<u>5</u>
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c.	<u>Good & sufficient</u>
Lower Deck Beams & Fastenings	} <u>Good</u>	Keelsons	} <u>Good</u>	Sails	<u>nearly 3 suits</u>
Planksheers		Clamps and Shelves			Anchors
Sheerstrakes	} <u>Good</u>	Ceiling		Cables	<u>13"</u>
Topsides		Rudder		Hawsers and Warps	<u>10" 9.5"</u>
Wales	} <u>Good</u>	Copper	<u>Yel Met^r When put on Now over felt</u>	Standing & Running Rigging	
Plank (Bottom) and Counter					

General Observations and Opinion, This vessel has been surveyed in conjunction with No 11 Intype for Continuation - with repairs noted is now in good & efficient order. Sheer & general form well preserved eligible to carry dry & perishable Cargoes & to be continued A1 for four years from expiry of original Class.
 Thomas Alexander

The Amount of Fee..... £ 5 : - : is received by me, J. M. M. Intype
 Special..... 3 : 3 :
 Certificate (if required) : 5 :

Committee's Minute 20th June 1854

Character assigned Continued 1 for 4 years
1853



LON 634-0497