

19092

REPORT of SURVEY for REPAIRS.

No. 472 Survey held at London Date 5th May to 21st June 1854
on the Ship Ellenborough Master R. Thornhill
Tonnage 853 Built at New Castle When built 1842
By whom built T. & W. Smith Owners Watson & Co 29 Graham Street
Port belonging to London Destined Voyage Australia
If Surveyed Afloat or in Dry Dock Young Son & Co Dry Dock & Afloat

Last Survey, No. 18520 Port London Classed 12 A1

REPAIRS at present executed under special survey for Continuation
vide Section 34 & sanction of Section 39 - Planksheers Sheer
Streak Upper Barks & Wales scraped bright & upper Courses of bottom
dubbed to Light Water line Renewed - 46 ft second length of Main
Keelson forward of Teak 15 ft Apron of Teak & Stemson Timber of
B^o Oak Knight heads & Hauser Timbers all renewed of B^o Oak - 31 Wale
forward renewed of Mahogany & B^o Oak & 3 Iron refastened
renewed on Starboard side 12 Shifts in Sheer Streak & 6 Shifts in Wale
on Starboard side 11 Wood & 1 Shift - Sheer Streak & 2 in Wale all the
above with Teak 23 Wale Ceiling in Top Gall Forecastle & Turst Decks
renewed of Teak also Wale of Shelf & Waterways in Upper & Lower Deck
of B^o Oak Upper & Lower Decks renewed round bows - 9 Shifts Top Gall
Forecastle outside plank renewed with Teak Part - Retrenched
in Topsides & entirely in Wale Buttocks & bottom down to 8 Strakes
from Keel with Australian Gum Wood - finally the vessel Caulked
from Keel to inside the Waterways & Resheathed with Gal Metal
over paper. - The State of the Main Deck & Waterways
Turn over

Present Condition of the

Decks	} Good	Treenails	Renewed	Rid ^g Bett	} Good & Sufficient
Waterways		Breasthooks and Stemson	part new	Windlass and Capstan & D W	
Comings		Transoms, Pointers, and Crutches	good	Pumps 4. 2 are new	
Upper Deck Beams & Fastenings	} Good & Firm	Timbers of the Frame	Good	Boats 4	} Good & Sufficient
Lower Deck Beams & Fastenings		Keelsons	— D	Masts, Yards, &c.	
Planksheers	} Good	Clamps and Shelves	D	Sails full double suit	
Sheerstrakes		Ceiling	D	Anchors No. of well formed	
Topsides		Rudder	D	Cables B ^o	
Wales	} Good	Copper	Gal ^y Met	Hawsers and Warps 9, 7½ 4½	} Good & Sufficient
Plank (Bottom) and Counter		When put on	Now	Standing & Running Rigging refitted	

General Observations and Opinion, Now Surveyed in conformity with the Rules Section 34
for Continuation - Is in efficient & good order Sheer & form
unaltered & eligible in our opinion to Class A1 for Four
Years from expiry of original period

The Amount of Fee.....£ 5 : - : is received by me,
Special..... 5 : 5 : -
Certificate (if required) : 5 : -

Committee's Minute 30th June 1854
Character assigned 12 A1 Continued 4

1909 2 Low

Upper & Lower deck Beams & fastenings with the planks through which
they pass - Floors & Frame timbers Nelson - Sheer Strake Topsides
Males & outside plating - Ceiling Skyl & Clempns inner surface
of outside plank where seen were all otherwise to the
above noted parts repaired in sound & good condition
Where seen



© 2019

Lloyd's Register
Foundation